

\$ 139.10

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-22460-00-00
Spot: SESWSE Sec/Twnshp/Rge: 8-15S-22W
400 feet from S Section Line, 1720 feet from E Section Line
Lease Name: WERTH Well #: 1
County: TREGO Total Vertical Depth: 4280 feet

Operator License No.: 31691
Op Name: CORAL COAST PETROLEUM, L.C.
Address: 8100 E 22ND ST N BLDG 600, STE R
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	219	0	w/165 sxs cmt
T1	2.375	4190		
PROD	5.5	4278	0	w/335 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/11/2010 1:30 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: BILLY Company: CORAL COAST PETROLEUM, L.C. Phone: (316) 269-1233

Proposed Plugging Method: Ordered 375 sxs 60/40 pozmix - 4% gel - 500# hulls - 15 sxs gel. D.V. Tool at 1660'.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/11/2010 4:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Tied onto the 5 1/2" casing - pumped 80 sxs cement with 300# hulls - followed with 13 sxs gel - followed with 120 sxs cement. Shut in 1800# P.S.I. - full. Tied onto backside - full.

Perfs:

Top	Bot	Thru	Comments
4194	4198		

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 16 2010
CONSERVATION DIVISION
WICHITA, KS

INVOICED

DATE 2/24/10
INV NO. 2010060770

Remarks: SWIFT SERVICES, INC.-TICKET #17412.

Plugged through: CSG

District: 04

Signed [Signature]
(TECHNICIAN) CM

CORAL COAST PETR LC
WICHITA KS 67226

8-15S-22W
400'FSL & 1720'FEL, SEC
KANSAS

#1 WERTH

City: TREGO

Spot NW SE SW SE API 15-195-22460

Site: 8-1/4 N & 2-3/4 W OF BROWNELL KS

Lat/Long: 38.75590 -99.78860

Field: GSL

FR: 06/08/2007 Spd: 06/23/2007 Drig Cp: 07/01/2007 Issued: 01/28/2008 Revised: 01/28/2008

Copyright 2008 Independent Oil & Gas Service, Inc. Wichita, KS

Side 1

IP Status:

OIL, CHER, INTV NA, 11/1/2007

Contr: MURFIN DRILLING #8

Elev: 2275 GL

Formation Tops: (L-Log, S-Sample, D-Driller)

NO TOPS RPTD

RTD

4280 -2005

Csg: 8-5/8" 250+ (ALT 2), PROD CSG NA

Finds:

COMMENT: PROPOSED START 6/18/2007; MI &
RURT 6/23/2007

NO CORES

DSTS TAKEN - DETAILS NA

Comp Info: TRGT ZN: CHER, CONG (OIL), PTD

4300 (MISS), MICT - CO, PF (CHER) INTV NA, SWB
LD, GSO, POP, OIL WELL (POTENTIAL NOT RPTD),

11/1/2007 - TIGHT HOLE - NO OTHER INFO

AVAILABLE - TEMP COMP 1/28/2008