

\$ 149.50

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-077-21525-00-00  
Spot: N2SW Sec/Twnshp/Rge: 20-33S-6W  
1980 feet from S Section Line, 1320 feet from W Section Line  
Lease Name: TRUBY Well #: 1  
County: HARPER Total Vertical Depth: 4600 feet

Operator License No.: 31933  
Op Name: M E KLEIN & ASSOCIATES, INC  
Address: PO BOX 721436  
NORMAN, OK 73070

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	293		200 SX CMT
T1	2.375	4520		
PROD	4.5	4597	2782	125 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/24/2009 8:00 AM  
Plug Co. License No.: 33728 Plug Co. Name: KING'S WELL SERVICE, LLC  
Proposal Rcvd. from: KING GOFF Company: KINGS WELL SERVICE Phone: (580) 363-3912

Proposed Plugging Method: SET CIBP 50' ABOVE PERFS, RECOVER CASING, 35 SKS 1100', 35 SKS 700', CIRCULATED CMT FROM 350-0

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL  
Date/Time Plugging Completed: 04/25/2009 5:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

A CIBP WAS SET AT 4400' AND CAPPED WITH 2 SKS OF CMT. THE CASING WAS RECOVERED FROM 2782' AND PULLED TO 1113', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 715', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 350', WHERE CMT WAS CIRCULATED TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
4456	4476	CSG	

INVOICED  
DATE 2/25/10  
INV. NO. 2010060812

RECEIVED  
FEB 18 2010  
KCC WICHITA

Remarks: ALLIED CEMENTING #30610  
Plugged through: CSG

District: 02

Signed  (TECHNICIAN)

JK