

\$ 112.94

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-23986-00-01  
Spot: W2SWNE Sec/Twnshp/Rge: 20-18S-11W  
3540 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: KRIER B Well #: 2  
County: BARTON Total Vertical Depth: 3475 feet

Operator License No.: 9951  
Op Name: KRIER, KIRBY OIL, INC.  
Address: 1043 NE 80TH RD  
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	342	0	w/165 sxs cmt
PROD	4.5	3474	0	w/165 sxs cmt

Well Type: EOR UIC Docket No: E25665.1 Date/Time to Plug: 12/07/2009 8:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: KIRBY KRIER Company: KRIER, KIRBY OIL, INC. Phone: (620) 587-3810

Proposed Plugging Method: Ordered 225 sxs 60/40 pozmix - 4% gel - 400# hulls - 9 sxs gel.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/07/2009 6:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:  
Ran tubing to 3050' - tied to tubing - pumped 9 sxs gel - followed with 40 sxs cement and 100# hulls.  
Pulled to 1307' - pumped 40 sxs cement with 100# hulls.  
Pulled to 700' - pumped 130 sxs cement with 100# hulls - circulated out backside and casing.  
Pulled tubing - squeezed to Max. P.S.I. 300#. Shut in.

Perfs:  
**INVOICED**  
DATE 2/25/10  
INV. NO. 2010060813

RECEIVED  
DEC 14 2009  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Bruce Rodie  
(TECHNICIAN) CM

DEC 11 2009

ROBERT L. SHAW  
2770 BERMUDA CIRCLE #2 'B' KRIER


20-18-11W  
C W/2 SW NE

COLORADO SPRINGS, CO 80917

CONTR DUKE DRILLING CTY BARTON

GEOLOGIST RICHARD HARPER FIELD FEIST NORTH

ELV 1817 KB SPD 7/20/85 CARD ISSUED 11/14/85 IP P 15 BO & 5 BWPD  
1812 GL DRLG COMP 7/24/85 CONG 3398-3401



LOG	Tops	Depth/Datum
HEEB		2970-1153
TOR		2988-1171
DOUG		3003-1186
BR LM		3083-1266
LANS		3097-1280
BKC		3361-1544
ARB		3405-1588
RTD		3475-1658

API 15-009-23,986

8 5/8 " 342 / 165SX, 4 1/2 " 3474 / 165SX

NO CORES OR DST'S

MICT - CO, PF-(CONG) 3398-3401, W / 2 SPF, AC 250G (15% FE), SWB DWN, SO, PF (CONG) 3384-93, W / 2 SPF, AC 500G (15% FE), SWB DWN, NON-COMMERCIAL, PF (LKC) 3306-08, W / 2 SPF, AC 250G (15% NE), SWB DWN, RE-AC 1000G (15% SGA), SWB DWN, NON-COMMERCIAL, PF (LKC) 3143-36 & 3124-27, W / 2 SPF, AC 250G (15% NE), SWB DWN, RE-AC 5500G (20% SGA), SWB DWN, NON-COMMERCIAL, POP, P 15 BO & 5 BWPD, 8/9/85

COPYRIGHT 1985  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS