

\$ 78.75

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-20147-00-01
Spot: S2SWSE Sec/Twnshp/Rge: 4-21S-14W
330 feet from S Section Line, 1980 feet from E Section Line
Lease Name: ASHER Well #: 1 OWWO
County: STAFFORD Total Vertical Depth: 2423 feet

Operator License No.: 6039
Op Name: L.D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	425		
PROD	4.5	2405	0	WITH 225 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/16/2009 8:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: SAND BOTTOM TO 2300' & 4 SX CMT. PERFORATE 4 1/2" @ 980'. PUMP CMT DOWN CASING & CIRCULATE UP SURFACE PIPE. NOT PULLING CASING DUE TO CEDAR HILLS FLOW.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/16/2009 10:16 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED BOTTOM TO 2280' & DUMP 4 SX CMT WITH DUMP BAILER. PERFORATED 4 1/2" @ 980'. PUMPED 430 SX CMT DOWN THE 4 1/2" CIRCULATED CMT TO SURFACE UP 8 5/8" X 4 1/2" ANNULUS. CLOSED IN 8 5/8" AND SQUEEZED WELL TO 350 PSIG.

Perfs:

Top	Bot	Thru	Comments
2354	2362		

INVOICED
DATE 2/25/10
INV. NO. 2010060814

RECEIVED
DEC 24 2009
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.
Plugged through: CSG

District: 01

Signed Richard W. Lacey
(TECHNICIAN)

RECEIVED
DEC 18 2009
KCC DODGE CITY

Form CP 273