

\$ 150.³¹

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-21101-00-01
Spot: E2W2SWNE Sec/Twnshp/Rge: 9-16S-27W
1980 feet from N Section Line, 2100 feet from E Section Line
Lease Name: LANG 1 Well #: OWWO
County: LANE Total Vertical Depth: 4625 feet

Operator License No.: 6039
Op Name: L.D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	777		WITH 475 SX CMT
DVT		1686		CMT TO SURFACE
PROD	5.5	4165	0	WITH 400 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/29/2009 11:00 AM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: MIKE KASSELMAN Company: LD DRILLING Phone: (620) 793-3051

Proposed Plugging Method: 20 SX GEL - 100# HULLS - 25 SX CMT @ 4450'. PLUG AT 2100' WITH 25 SX CMT. PLUG AT 1300' WITH 25 SX CMT. PLUG AT 780' WITH 25 SX CMT. PLUG AT 60' WITH 20 SX CMT. CHECK 8 5/8" X 5 1/2" WITH 50 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/29/2009 4:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 24 SX GEL - 100# HULLS & 20 SX CMT @ 4450'. 1ST PLUG AT 2100' WITH 25 SX CMT. 2ND PLUG AT 1300' WITH 25 SX CMT. 3RD PLUG AT 840' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 15 SX CMT. 5TH PLUG PUMP 16 SX CMT DOWN ANNULUS TO FILL.

Perfs:

Top	Bot	Thru	Comments
4546	4552		

INVOICED
DATE 2/25/10
INV. NO. 2010060814

RECEIVED
JAN 19 2010

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

KCC WICHITA

Plugged through: TBG

District: 01

Signed _____

(TECHNICIAN)

RECEIVED

JAN - 6 2010

KCC DODGE CITY

Form CP-21