

\$133.90

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-00111-00-01
Spot: NWNWNW Sec/Twnshp/Rge: 34-27S-5W
330 feet from N Section Line, 330 feet from W Section Line
Lease Name: YOUNG G Well #: 2-34 RE
County: KINGMAN Total Vertical Depth: 4120 feet

Operator License No.: 5214
Op Name: LARIO OIL & GAS COMPANY
Address: 301 S MARKET ST
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	263		
PROD	5.5	3973	2875	155 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE Phone: (620) 257-2719

Proposed Plugging Method: AS PER KCC

Plugging Proposal Received By: _____ Witness Type: PARTIAL
Date/Time Plugging Completed: 01/14/2010 10:00 AM KCC Agent: B. J. HOPE

Actual Plugging Report:
SANDED BACK TO 3710' TOPPED SAND WITH 5 SXS OF CEMENT. RIPPED CASING PIPE OFF AT 2875', THEN PULLED CASING TO 900' SPOTTED 35 SXS OF CEMENT WITH 3% CC, WAITED 1.5 HOURS THEN TAGGED CEMENT AT 650', PULLED CASING TO 450' SPOTTED 35 SXS CEMENT, PULLED CASING TO 296' CIRCULATED TO SURFACE WITH 90 SX OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
3763	3773	CSG	

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 25 2010
CONSERVATION DIVISION
WICHITA, KS
INVOICED
DATE 2/25/10
INV. NO. 2010060816

Remarks: QUALITY CEMENTING TICKET #3985, 60/40 POS MIX WITH 4% GEL. GPS LAT: 37.66003, LONG: 97.86108
Plugged through: CSG

District: 02 Signed B. J. Hope (TECHNICIAN)

SK