

11.09

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-197-20167-00-00  
Spot: NWSESENW Sec/Twnshp/Rge: 32-14S-10E  
3020 feet from S Section Line, 3040 feet from E Section Line  
Lease Name: ELDRIDGE Well #: 32-1  
County: WABAUNSEE Total Vertical Depth: 3418 feet

Operator License No.: 3842  
Op Name: LARSON ENGINEERING, INC. DBA LA  
Address: 562 W STATE RD 4  
OLMITZ, KS 67564

| String | Size  | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| SURF   | 8.625 | 310        |             | 156 SX   |
| PROD   | 5.5   | 3415       |             | 100 SX   |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/06/2009 8:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: TOM LARSON Company: LARSON ENGINEERING, INC. Phone: (785) 798-4848

Proposed  
Plugging  
Method:

AS DIRECTED BY DISTRICT 3 OFFICE

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: NONE  
Date/Time Plugging Completed: 10/07/2009 5:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

Perforated the 5.5" casing at 1500'. Had 2 7/8" tubing placed at 3175'. Pumped 35 sacks of cement at 3175'. Pulled the 2 7/8" tubing up to 1495' and pumped 25 sacks of cement. Pulled the 2 7/8" tubing up to 351' and circulated 100 sacks of cement to surface.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 3251 | 3255 |      | VIOLA    |

RECEIVED  
FEB 08 2010  
KCC WICHITA

INVOICED  
DATE 2/25/10  
INV. NO. 2010060817

Remarks:

Plugged through: TBG

District: 03

Signed Taylor C. Herman  
(TECHNICIAN)