

\$ 87.65

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-075-10064-00-01
Spot: NWSE Sec/Twnshp/Rge: 18-22S-41W
2029 feet from S Section Line, 1969 feet from E Section Line
Lease Name: HCU 1821-D Well #: SWD
County: HAMILTON Total Vertical Depth: 2697 feet

Operator License No.: 33999
Op Name: LINN OPERATING, INC.
Address: 600 TRAVIS STE 5100
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	124		WITH 150 SX CMT
PKR		2320		
PROD	4.5	2697	0	WITH 100 SX CMT

Well Type: SWD UIC Docket No: D11482.0 Date/Time to Plug: 12/04/2009 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/07/2009 3:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PBTD @ 2036' IN 2 3/8" FIBERGLASS TBG. LINER: 2 3/8" FIBERGLASS TBG. 1ST PLUG 2 3/8" FIBERGLASS TBG WAS CEMENTED IN 4 1/2" CASING WITH 105 SX CMT FROM THE BOTTOM & 100 SX CMT FROM THE TOP. 12/1/09: RAN BOND LOG FROM 2036-0'. FOUND CMT INSIDE 4 1/2" X 2 3/8" ANNULUS FROM 2036-400'. CMT OUTSIDE OF 4 1/2" CASING FROM 1530' - 1290' & 770' TO 550'. PUMPED 25 SX CMT MIXED WITH 25# HULLS. DID NOT HOLD. 2ND PLUG PUMPED 30 SX CMT WITH 75# HULLS. TAGGED TOC @ 1192'. PERFORATED 4 HOLES @ 1072' & PUMPED 90 SX CMT W/50# HULLS & 10 SX CMT. SHUT IN PRESSURE 650#. 3RD PLUG PERFORATED 2 3/8" TBG @ 293'. CIRCULATED CMT TO SURFACE WITH 100 SX CMT. CLOSED SURFACE CSG VALVE & SQUEEZED ADDITIONAL 50 SX CMT. SHUT IN PRESSURE 200#. 4TH PLUG PUMPED ADDITIONAL 35 SX CMT DOWN 2 3/8" X 4 1/2" ANNULUS.

Perfs:

Top	Bot	Thru	Comments
2347	2367		

INVOICED
DATE 2/25/10
INV. NO. 2010060819
RECEIVED
JAN 07 2010

Remarks: USED CLASS A CMT & 60/40 POZMIX 4% GEL BY ALLIED.

KCC WICHITA

Plugged through: TBG

District: 01

Signed Ken Jehlik
(TECHNICIAN)

RECEIVED
DEC 29 2009
KCC DODGE CITY