

\$162.66

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-22285-00-00
Spot: NESENWSW Sec/Twnshp/Rge: 31-28S-15W
1660 feet from S Section Line, 1070 feet from W Section Line
Lease Name: CURTIS Well #: 1
County: PRATT Total Vertical Depth: 5005 feet

Operator License No.: 31980
Op Name: LOTUS OPERATING COMPANY, L.L.C.
Address: 100 S MAIN STE 420
WICHITA, KS 67202

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-----------------|
| CIBP | | 4650 | | WITH 2 SX CMT |
| SURF | 8.625 | 742 | | WITH 200 SX CMT |
| COND | 10.75 | 283 | | WITH 250 SX CMT |
| PROD | 5.5 | 4920 | 2705 | WITH 215 SX CMT |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/04/2010 9:00 AM
Plug Co. License No.: 5112 Plug Co. Name: MIDWESTERN WELL SERVICE, INC.
Proposal Rcvd. from: ROBIN BROWN Company: LOTUS OPERATING Phone: (316) 546-4801

Proposed Plugging Method: SET CIBP @ 4650' WITH 2 SX CMT. PLUG AT 1020' WITH 15 SX GEL & 50 SX CMT. PLUG AT 760' WITH 50 SX CMT. PLUG AT 300' WITH 40 SX CMT. PLUG AT 60' WITH 20 SX CMT. CHECK 8 5/8" X 10 3/4" ANNULUS FOR CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/04/2010 1:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4650' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. RAN BOND LOG ON 8 5/8" CASING. TOC @ 267'. RAN TBG IN. 1ST PLUG AT 1020' WITH 15 SX GEL & 50 SX CLASS A CMT W/4% CC. 2ND PLUG AT 760' WITH 50 SX CLASS A CMT W/4% CC. 3RD PLUG LAY TBG DOWN. PERFORATE 8 5/8" @ 220'. LOAD HOLE, ESTABLISH CIRCULATION UP BACKSIDE OF 8 5/8" WITH WATER. TOP JOINT OF 8 5/8" STARTED COMING OUR OF HOLE WITH 100# OF LIFTING PRESSURE. SHUT DOWN & SET 8 5/8" PIPE BACK DOWN. RUN TBG BACK INTO 230'. PUMP DOWN TBG WITH 110 SX CMT FILLING 8 5/8" & 8 5/8" X 10 3/4" ANNULUS WITH CMT.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|-------------|
| 4663 | 4698 | | MISSISSIPPI |

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 29 2010
CONSERVATION DIVISION
WICHITA, KS

INVOICED
DATE 2/25/10
INV. NO. 2010060820

Remarks: USED CLASS A CMT & 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED
JAN 14 2010

KCC DODGE CITY