

#127.47

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-00420-00-03
Spot: NWSW Sec/Twnshp/Rge: 11-22S-8W
1902 feet from S Section Line, 4720 feet from E Section Line
Lease Name: JUSTUS SWD Well #: 1
County: RENO Total Vertical Depth: 3922 feet

Operator License No.: 31980
Op Name: LOTUS OPERATING COMPANY, L.L.C.
Address: 100 S MAIN STE 420
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	242		150 SX
PROD	4.5	3922	1510	150 SX

Well Type: SWD UIC Docket No: D26877.0 Date/Time to Plug:
Plug Co. License No.: 5112 Plug Co. Name: MIDWESTERN WELL SERVICE, INC.
Proposal Rcvd. from: ROBIN BROWN Company: LOTUS Phone: (620) 546-4801

Proposed Plugging Method: AS PER KCC RULES AND REGULATIONS

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL
Date/Time Plugging Completed: 12/28/2009 9:00 AM KCC Agent: B. J. HOPE

Actual Plugging Report:

CIBP SET @ 3476 2 SX OF CEMENT PLACED ON TOP. SHOT CASING OFF AT 1510', PULLED CASING TO 1238' SPOTTED 35 SXS OF CEMENT WITH 4% CC. WAITED 1.5 HOURS TAGGED CEMENT AT 1000'. PULLED CASING TO 742' SPOTTED 35 SX OF CEMENT. PULLED CASING TO 295' CIRCULATED 145 SXS OF CEMENT TO SURFACE. TOP PLUG FELL BACK 60', PLACED 10 SXS INSIDE SURFACE TO TOP OFF CASING.

Perfs:

Top	Bot	Thru	Comments
3870	3900	CSG	
3526	3580	CSG	

RECEIVED
FEB 18 2010
KCC WICHITA

INVOICED
DATE 2/25/10
INV. NO. 2010060821

Remarks: ALLIED CEMENTING TICKET #037086

Plugged through: CSG

District: 02

Signed B.J. Hope
(TECHNICIAN)

JK