

157.79

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-10375-00-00
Spot: SENESE Sec/Twnshp/Rge: 36-34S-13W
1650 feet from S Section Line, 330 feet from E Section Line
Lease Name: STERLING B Well #: 2
County: BARBER Total Vertical Depth: 4855 feet

Operator License No.: 31980
Op Name: LOTUS OPERATING COMPANY, L.L.C.
Address: 100 S MAIN STE 420
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4430		WITH 2 SX CMT
SURF	8.625	300		WITH 250 SX CMT
PROD	5.5	4850	2340	WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/14/2010 1:00 PM
Plug Co. License No.: 5112 Plug Co. Name: MIDWESTERN WELL SERVICE, INC.
Proposal Rcvd. from: ROBIN BROWN Company: LOTUS OPERATING Phone: (620) 546-4801

Proposed Plugging Method: CIBP @ 4400' WITH 2 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 330' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/14/2010 2:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

UNABLE TO GET CIBP TO 4700' DUE TO SCALE PIPE. SET @ 4430'. EST. TOC ON 5 1/2" @ 4100'.SET CIBP @ 4430' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 620' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 312' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4785	4825		MISSISSIPPI

RECEIVED
FEB 08 2010
KCC WICHITA

INVOICED

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.
Plugged through: TBG

DATE 2/25/10
INV. NO. 2010060821

District: 01

Signed Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED
FEB - 4 2010
KCC DODGE CITY

RAWL