

\$143.25

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-21345-00-00
Spot: NENESW Sec/Twnshp/Rge: 15-31S-8W
2310 feet from S Section Line, 2310 feet from W Section Line
Lease Name: CRAMER Well #: 1-15
County: HARPER Total Vertical Depth: 4407 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 8080 E CENTRAL STE 300
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	224		175 SXS CMT
PROD	5.5	4405	3140	100 SXS CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/22/2010 10:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 4350' AND 5 SKS OF CMT. RECOVER CASING. SPOT PLUGS AT 35 SKS 1250', 35 SKS 900', CIRC CMT FROM 275-0.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 01/22/2010 12:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND TO 4340', AND CAPPED WITH 5 SKS OF CMT. THE CASING WAS RECOVERED FROM 3140', AND PULLED TO 1250', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 900', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 275', WHERE CMT WAS CIRCD TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4397	4407	CSG	

INVOICED
DATE: 2/26/10
INV. NO. 2010060823

RECEIVED
JAN 27 2010
KCC WICHITA

Remarks: QUALITY WELL CEMENTING 60/40 4% GEL

Plugged through: CSG

District: 02

Signed [Signature]
(TECHNICIAN)

JK