

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-41

NE, Sec. 14, T 11 S, R 18 WE

660 feet from N/S section line

990 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5229

Lease Name Hugh Well # 2

Operator: Phillips Petroleum Co.
Name &
Address Box 287, Great Bend, Ks. 67530

County Ellis

Well Total Depth 3377 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8" feet 1145'

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Services License Number 5287

Address E. 8th. St. Hays, Ks. 67601

Company to plug at: Hour: 10:00 AM Day: 8 Month: 11 Year: 1982

VERBAL PLUGGING ORDERS GIVEN TO H. J. Stearns

(company name) _____ (phone) 316-793-8421

were: Order 360 sacks 50 permix - 4% Gel. 3% Col. U. & 2 sacks bull's, 17 sacks Gel.

Signed [Signature]
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 2:45 PM Day: 8 Month: 11 Year: 1982

ACTUAL PLUGGING REPORT Ran 2" tubing to 3359' & spotted 25 sacks cement to 3048', pulled tubing to 3048' & spotted 17 sacks Gel. to 1512', pulled tubing to 1512' & circulated cement to surface. Pumped in 8 5/8" S.P. 210 sacks cement w/ 2 sacks bull's in cement.

Maximum pressure 1000 pounds

Remarks: _____

RECEIVED
STATE CORPORATION COMMISSION
NOV 22 1982
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (did / ~~did not~~) observe this plugging.

Signed [Signature]
(TECHNICIAN)

INVOICED
11-24-82
1732-W