

15-051-05732-00-80
2-28
164A

To: **6 062359**
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 19-
NE . SEC. 14 , T 11 S, R 18 W ^{XXX}

3300 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 6568
Operator: Kaiser Francis Oil Co.
Name & Address: Box 21468
Tulsa, OK 74121-1468

Lease Name Hugh Well # 1
County Ellis 112.28
Well Total Depth 3455 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 1134

Abandoned Oil Well ^{XXX} Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pullers Inc. License Number 4635
Address Box 768 Great Bend, K.S 67530

Company to plug at: Hour: 10:00AM Day: 28 Month: Feb. Year: 19 91

Plugging proposal received from Gary Burke
(company name) Great Bend Casing Pullers Inc. (phone) 316-793-9711
were: Order 300 sks 60/40 poz 8% gel 5 sks hulls.

RECEIVED
STATE CORPORATION COMMISSION

MAR 22 1991

4 1/2 liner from 3291 to 3450 w/50 sks.

CONSERVATION DIVISION
WICHITA, KANSAS

Plugging Proposal Received by Gilbert G. Scheck
(TECHNICIAN)

Plugging Operations attended by Agent?: All XX Part None
Operations Completed: Hour: 2:00 PM Day: 28 Month: Feb. Year: 19 91

ACTUAL PLUGGING REPORT 8 5/8 set at 1134 w/350 sks. 5 1/2 set at 3355
w/200 sks. top perf at 3355. Plugged bottom w/sand and 5 sks cement to
3300. Shot pipe two times and recovered 1800. Pumped in 8 5/8 25 sks
cmemt followed w/5 sks hulls in 275 sks cement w/1000 psi.

Remarks: Allied. Ran line to 1500.
(If additional description is necessary, use BACK of this form.)

INVOICED
If (did or did not) observe this plugging.

Signed Gilbert G. Scheck E.A.S.
(TECHNICIAN)
Gilbert Scheck

DATE APR 02 1991

INV. NO. 31277