

6-20 '5-065-01918-00-00

To: **6 031374**  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-  
N/2N/2 NW, SEC. 11, T. 10 S, R. 25 W W

TECHNICIAN'S PLUGGING REPORT

Operator License # 5010  
Operator: Knighton Oil Co. Inc.  
Name & Address 710 Petroleum Bldg.  
Wichita, Ks. 67202

4950 feet from S section line  
3960 feet from E section line  
Lease Name east Elrick Unit 1-6  
County Graham  
Well Total Depth 4023 feet  
Conductor Pipe: Size 8 5/8 inches  
Surface Casing: Size 8 5/8 inches

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Express Well Service License Number Tag 2287

Address Victoria, Ks.

Company to plug at: Hour: Pm Day: 20 Month: June Year: 19 90

Plugging proposal received from Carl Gilpin

(company name) Knighton Oil (phone) \_\_\_\_\_

were: 8 5/8 set at 200 w/140 sks. 4 1/2 set at 4023 w/150 sks. Sq at 1610 w/200 sks

PBTD 3976. Rods and tubing fish at 3298. Casing parted 1200 +/- Order

workstring, 300 sks 65/35 poz 8% gel 500 lbs. hulls.

Allied Cement Co. Wellbrock Water Truck.

Plugging Proposal Received by Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 6:15PM Day: 20 Month: June Year: 19 90

ACTUAL PLUGGING REPORT Ran workstring to 2200. Mixed and pumped cement blend to

circulate. Laid down tubing. Sq 4 1/2 casing w/total of 175 sks cement blend w/hulls

mixed into max psi 800 lbs. Close in 400 lbs. Sq 8 5/8 annulus w/25

blend to max psi 400 lbs..

Close in 150 lbs. Plug complete.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 13 1990

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 7-24-90

INV. NO. 28717  
6-20

*Phil S.*

Signed Carl Goodrow  
(TECHNICIAN)