

~~6-050107~~

15-065-01911-00-01
7-30
E-15,410
200
R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- -
NE NW SE /4 SEC. 11, 10 S, 25 W
2310 feet from S section line
1650 feet from E section line

Operator license# 5010 Lease East Elrick well # 3-1

Operator: Knighton Oil Company County Graham

Address: 710 Petroleum Bldg. Well total depth 3959 feet
Wichita, Kansas 67202 Conductor Pipe: inch @ feet
316-264-7918 Surface pipe 8 5/8 Inch @ 205 feet

128.66

Aband. oil well , Gas well , Input well X, SWD , D & A

Plugging contractor: Allied Cementing Company License#

Address:

Company to plug at: Hour: PM Day: 30 Month: July Year: 1991

Plugging proposal received from: Carl Gilpin

Company: Knighton Oil Company phone:

Were: Order 50 sks. Class A Common, 365 sks. 65/35 Pozmix 6% gel.

Plugging Proposal Received by: Marvin L. Miller

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 1:30 pm, Day: 30, Month: July, Year: 1991

Actual plugging report: Ran tbq. to 3702' pumped 50 sks. common cement,
pulled 25 jts. (750') to 2950'. Pumped 100 sks. 65/35 poz 6% gel, pulled
60 jts. tbq. to 1150'. Pumped 65 sks cement down tbq. cement circulated.
Pulled rest of tbq. tied onto 4 1/2 csg, squeezed with 50 sks. cement at
500 psi. with 200 shut-in psi. Tied onto backside squeezed with 150 sks.
cement at 150 psi. and 50 shut-in psi.

RECEIVED
STATE CORPORATION COMMISSION

8-21-1991
AUG 21 1991

Remarks:

CONSERVATION DIVISION
Wichita, Kansas

I did not observe the plugging.

Marvin L. Miller

INVOICED
DATE 8-28-91
INV. NO. 32876

J.S.

Marvin L. Miller
Form CP-2/3