

\$ 120.25

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-23837-00-00
Spot: SENESENW Sec/Twnshp/Rge: 2-10S-18W
1730 feet from N Section Line, 2360 feet from W Section Line
Lease Name: COLLINS TRUST Well #: 2-1
County: ROOKS Total Vertical Depth: 3700 feet

Operator License No.: 32639
Op Name: CORAL PRODUCTION CORPORATION
Address: 1600 STOUT ST STE 1500
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	227		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 01/18/2010 3:00 PM
Plug Co. License No.: 34233 Plug Co. Name: MAVERICK DRILLING LLC
Proposal Rcvd. from: MARK Company: CORAL PRODUCTION CORPORATI Phone: (202) 623-3573

Proposed Plugging Method: Ordered 245 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: BRUCE BASYE WitnessType: NONE
Date/Time Plugging Completed: 01/18/2010 5:00 PM KCC Agent: BRUCE BASYE

Actual Plugging Report:

1st. Plug at 3644' w/40 sxs.
2nd. Plug at 1480' w/25 sxs.
3rd. Plug at 890' w/100 sxs.
4th. Plug at 280' w/40 sxs.
5th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.

Perfs:

RECEIVED
JAN 21 2010
KCC WICHITA

INVOICED
DATE 2/24/10
INV. NO. 2010060771

Remarks: QUALITY OIL WELL CEMENTING COMPANY.
Plugged through: DP

District: 04

Signed Bruce D. Basye
(TECHNICIAN) CM

JAN 19 2010