

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-169-20107-00-00
Spot: NWNWNW Sec/Twnshp/Rge: 29-16S-1W
5076 feet from S Section Line, 5028 feet from E Section Line
Lease Name: PETERSON Well #: 1
County: SALINE Total Vertical Depth: 2675 feet

Operator License No.: 6901
Op Name: D S & W WELL SERVICING, INC.
Address: 1822 24TH STREET
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	7	137		65 SXS
PROD	4.5	2673		80 SXS

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: TIM DICKSON Company: _____ Phone: (620) 793-5838

Proposed Plugging Method: AS PER KCC ORDERS

Plugging Proposal Received By: _____ Witness Type: PARTIAL
Date/Time Plugging Completed: 01/12/2010 3:00 PM KCC Agent: SHANE JONES

Actual Plugging Report:

1/5/10 DS&W DROPPED SAND. 1/6/2010 PERORATED CASING. 1/12/2010 DS&W USED DUMP BAILER TO CAP THE SAND W/5 SXS CEMENT. THEY TAGGED SAND @ 2245'. THEY RAN TUBING TO 270'. COPELAND CIRCULATED CEMENT UP THE CASING AND, THEN SHUT IT IN TO CIRCULATE CEMENT UP THE BACK SIDE. DS & W PULLED TUBING AND, COPELAND TOPPED OFF THE WELL. THEY USED 300 SXS OF 60/40 POS W/4% GEL TK #26323. 1/13/2010 TOP PLUG DOWN APPROX 50'. COPELAND USED 10 SXS OF 60/40 POS W/4% GEL TO TOP OFF CASING TODAY. TK #36324.

Perfs:

Top	Bot	Thru	Comments
2618	2644	CSG	
2638			


INVOICED
DATE 2/24/10
INV. NO. 2010060774

RECEIVED
JAN 22 2010
KCC WICHITA

Remarks: DENIED TA DUE TO HIGH FLUID LEVEL

Plugged through: TBG

District: 02

Signed  (TECHNICIAN)

SK