

87-13

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-169-20150-00-00
Spot: NWENW Sec/Twnshp/Rge: 29-16S-1W
5039 feet from S Section Line, 3725 feet from E Section Line
Lease Name: PETERSON Well #: 2
County: SALINE Total Vertical Depth: 2681 feet

Operator License No.: 6901
Op Name: D S & W WELL SERVICING, INC.
Address: 1822 24TH STREET
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	165		100 SX
PROD	5.5	2678		125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/13/2010 10:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: ED NEMNICK Company: D S & W WELL SERVICING Phone: (620) 793-5860

Proposed Plugging Method: SAND PERFS TO 2580' AND CAP WITH 5 SX'S CEMENT, PERFORATE @ 250' AND CIRCULATE CEMENT TO SURFACE.

Plugging Proposal Received By: _____ WitnessType: PARTIAL
Date/Time Plugging Completed: 01/13/2010 3:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SAND PERFS TO 2407' AND CAP WITH 5 SX'S CEMENT, PERFORATE @ 250'. RUN TUBING TO 270' AND CIRCULATE CEMENT TO SURFACE. SHUT VALVE ON TUBING-CASING ANNULUS, PUMP 225 SX'S CEMENT-- NEVER GOT CEMENT IN CASING-SURFACE CASING ANNULUS. PULL TUBING OUT & LET SET AWHILE AND PUMPED 75 MORE SX'S TO GET CEMENT RETURNS ON UP THE BACKSIDE OF CASING -- PRESSURED ON UP TO 500#'S AND SHUT DOWN.

Perfs:

Top	Bot	Thru	Comments
2630	2634	CSG	

RECEIVED
JAN 20 2010
KCC WICHITA

INVOICED
DATE 2/24/10
INV. NO. 2010060774

Remarks: 60-40 POZ, 4% GEL. LOG TECH #5917. COPELAND TICKET C-36321 GPS: LAT: 38.63750, LONG: 97.45860

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

✓ SK