

K 123.01

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-21155-00-00
Spot: NWNWNE Sec/Twnshp/Rge: 10-8S-23W
4950 feet from S Section Line, 2310 feet from E Section Line
Lease Name: JONES Well #: 2
County: GRAHAM Total Vertical Depth: 3785 feet

Operator License No.: 9067
Op Name: DAMAR RESOURCES, INC.
Address: 234 W 11TH STE A PO BOX 70
HAYS, KS 67601

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| SURF | 8.625 | 276 | 0 | 190 SX |
| PROD | 5.5 | 3782 | 0 | 200 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/31/2009 10:30 AM
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC
Proposal Rcvd. from: AVEN WEAVERLING Company: DAMAR RESOURCES, INC. Phone: (785) 625-0020

Proposed Plugging Method: Ordered 275 sxs 60/40 pozmix - 4% gel - 13 sxs gel - 500# hulls.
High fluid level. DV at 1958' circulated with 400 sxs.
Denied TA.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/31/2009 1:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Poe Servicing, Inc. RIH with tubing to 3414'.
Quality rigged to tubing and pumped 13 sxs gel - followed with 50 sxs 60/40 pozmix - 4% gel with 250# hulls mixed in.
Pulled tubing to 2000'. Quality rigged to tubing and pumped 100 sxs cement with 150# hulls mixed in.
Pulled tubing to 1000'. Quality rigged to tubing and mixed and pumped 80 sxs cement with 100# hulls to circulate cement to pit.
Pulled tubing. Topped off 5 1/2" casing with 15 sxs cement.
Hole standing full of cement.
Rigged to 8 5/8" casing - pumped 5 sxs cement.
Max. P.S.I. 200#. S.I.P. 200#.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3725 | 3729 | | OH |
| 3705 | 3706 | | |
| 3584 | 3586 | | |

RECEIVED
JAN 06 2010

INVOICED KCC WICHITA

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #3708.

DATE 2/24/10
INV. NO. 2010060775

Plugged through: TBG

District: 04

Signed [Signature]
(TECHNICIAN) CM

JAN 04 2010

THE MAURICE L. BROWN CO.

200 SUTTON PLACE

WICHITA, KS 67202

#2 JONES

10-8-23W


NW NW NE

CONTR ABERCROMBIE DRLG. INC. CTY GRAHAM

GEOL _____ FIELD FABRICIUS SOUTH

E 2270 KB CM 8/9/79 CARD ISSUED 1/24/80 IP P 25' B0 & 20 BWPD

LKC 3584-86 &
3705-29 OA



API 15-065-21,155

| LOG | TOPS | DEPTH | DATUM. |
|--------|------|-------|--------|
| SC | | 1927 | + 343 |
| HEEB | | 3498 | -1228 |
| TOR | | 3523 | -1253 |
| LANS A | | 3541 | -1271 |
| LANS B | | 3569 | -1299 |
| LANS D | | 3584 | -1314 |
| LANS E | | 3602 | -1332 |
| LANS G | | 3605 | -1335 |
| LANS H | | 3665 | -1395 |
| LANS I | | 3689 | -1419 |
| LANS J | | 3704 | -1434 |
| LANS K | | 3724 | -1454 |
| LANS L | | 3738 | -1468 |
| BKC | | 3746 | -1476 |
| LTD | | 3769 | -1499 |
| RTD | | 3785 | -1515 |

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

8-5/8" 2761/190sx, 5 1/2" 3791/650sx
DST (1) 3565-85 (LANS B)/60-60-60-60,
698' MSW, SIP 341-341#, FP 54-305/
305-323#, HP 1800-1764#, BHT 102°
DST (2) 3582-3605 (LANS D)/60-60-60-60
378' GIP, REC. 252' GCO, 126' HOCM
(GR 32°), SIP 359-359#, FP 27-108/
108-162#, HP 1782-1782#, BHT 108°
DST (3) 3605-25 (LANS G)/PKR FAILURE
DST (4) 3600-35 (LANS G)/60-60-90-90,
575' MSW, SIP 323-323#, FP 36-225/
225-296#, HP 1764-1764#, BHT 110°
DST (5) 3650-3700 (LANS H,I)/60-60-90-
90, 135' WM, SIP 1194-1185#, FP
36-72/72-108#, BHT 110°
DST (6) 3698-3740 (LANS J,K)/60-60-90-
90,
(OVER)