

115.67

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-25920-00-00
Spot: NESWSWSE Sec/Twnshp/Rge: 21-13S-16W
410 feet from S Section Line, 2010 feet from E Section Line
Lease Name: KARLIN FAMILY Well #: 1
County: ELLIS Total Vertical Depth: 3559 feet

Operator License No.: 9067
Op Name: DAMAR RESOURCES, INC.
Address: 234 W 11TH STE A PO BOX 70
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	219	0	150 sx
PROD	5.5	3558	2300	130 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/12/2010 10:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: AVEN WEAVERLING Company: DAMAR RESOURCES, INC. Phone: (785) 625-0020

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/12/2010 1:45 PM KCC Agent: PAT STAAB

Actual Plugging Report:
LK Wireline set CIBP at 3150' - topped with 5 sxs cement.
LK shot casing off at 2300'.
Pulled casing to 1115' - pumped 50 sxs 60/40 pozmix - 4% gel with 200# hulls.
Pulled casing to 573' - mixed and pumped 140 sxs 60/40 pozmix - 4% gel with 300# hulls to circulate cement to pit area.
Pulled rest of casing. Topped off with 30 sxs cement.
Hole standing full.

Perfs:

Top	Bot	Thru	Comments
3248	3252		LKC

RECEIVED
JAN 14 2010
KCC WICHITA

INVOICED

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #3518.

DATE 2/24/10
INV. NO. 2010060775

Plugged through: CSG

District: 04

Signed [Signature]
(TECHNICIAN)

CM

JAN 12 2010