

\$108.65

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-19100-00-00
Spot: NESWNE Sec/Twnshp/Rge: 19-16S-11W
3630 feet from S Section Line, 1650 feet from E Section Line
Lease Name: REDETZKE A A Well #: 4
County: BARTON Total Vertical Depth: 3343 feet

Operator License No.: 5088
Op Name: DARRAH, JOHN JAY, JR.
Address: 225 N MARKET STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	354	0	125 SX
PROD	5.5	3340	0	100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/28/2010 9:30 AM
Plug Co. License No.: 32098 Plug Co. Name: CLASSIC WELL SERVICE, INC.
Proposal Rcvd. from: GEORGE STOPPELWERETH Company: DARRAH, JOHN JAY, JR. Phone: (620) 726-4046

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 500# hulls.
Perfs: 1475' - 800' - 450'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/28/2010 1:40 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 3190' - pumped 100 sxs cement with 150# hulls.
Pulled tubing to 1475' - pumped 100 sxs cement with 200# hulls.
Pulled tubing to 800' - pumped 105 sxs cement with 150# hulls - cement circulated.
POOH. Hooked up to Braden head and pumped 25 sxs cement.
Max. P.S.I. 250#. S.I.P. 200#.
Topped off casing with 5 sxs.

Perfs:

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 01 2010
CONSERVATION DIVISION
WICHITA, KS

INVOICED

Remarks: COPELAND CEMENTING COMPANY-TICKET #37805.

DATE 2/24/10
INV. NO. 2010060776

Plugged through: TBG

District: 04

Signed Ray A Dinkel
(TECHNICIAN) CM

JAN 29 2010

GULF OIL

#1 A A REDETZKE

19-16-11W
NE SW NE

Contr. _____ BARTON County

E 1914 Comm 9-9-44 Comp 10-12-44 IP 432 BOPD: NW

Tops	Depth	Datum	Casing
			8" 354
HEEB	2964		5" 3340
OREAD	3002		
LANS	3075		1350' OIH/35"
			2000' OIH/3 hr
			Pmp 108 BO/6 hrs, NW
ARB	3340		
TD	3343		

+	+	+	+
+	+	+	+
+	+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS