

#175.86

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-21045-00-02
Spot: SWNWNE Sec/Twnshp/Rge: 21-32S-18W
1000 feet from N Section Line, 2310 feet from E Section Line
Lease Name: ACRES Well #: 3
County: COMANCHE Total Vertical Depth: 5411 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 1321 W 93 N PO BOX 360
VALLEY CENTER, KS 67147

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	663		WITH 310 SX CMT
COND	13.38	99		WITH 100 SX CMT
PROD	4.5	5512	3259	WITH 245 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/29/2009 9:40 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: STEVE BODINE PRODUCTI Company: DAYSTAR PETROLEUM Phone: (316) 755-3492

Proposed Plugging Method: PUMP 200# HULLS & 50 SX CMT @ 4314'. PLUG AT 1050' WITH 15 SX GEL & 50 SX CMT. PLUG AT 690' WITH 50 SX CMT. PLUG AT 300' WITH 40 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: RICHARD LACEY

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 12/29/2009 10:45 AM

KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Perfs:

12/23/09: PUMPED 150# HULLS & 50 SX CMT THROUGH PERFS. PRESSURED TO 1100# & HELD. 1ST PLUG AT 1090' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 690' WITH 50 SX CMT. 3RD PLUG AT 300' WITH 40 SX CMT. 4TH PLUG AT 40' WITH 20 SX CMT. CMT CIRCULATED BUT FELL BACK. TOC @ 373'. TOPPED OFF WITH 120 SX CMT.

Remarks: USED 60/40 POZMIZ 4% GEL BY COPELAND ACID.

Plugged through: CSG

RECEIVED
JAN 11 2010
KCC WICHITA
INVOICED
DATE 2/24/10
INV. NO. 2010060777

District: 01

Signed Eric MacLaren
(TECHNICIAN)

RECEIVED
JAN - 6 2010
KCC DODGE CITY

Form CP-2/3