

# 104.81

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-21193-00-00  
Spot: SESWSE Sec/Twnshp/Rge: 30-18S-6W  
330 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: PERRY B Well #: 1  
County: RICE Total Vertical Depth: 3225 feet

Operator License No.: 30931  
Op Name: DAYSTAR PETROLEUM, INC.  
Address: 1321 W 93 N PO BOX 360  
VALLEY CENTER, KS 67147

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	231		160 SXS CMT
PROD	4.5	3140		100 SXS CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/28/2010 10:30 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKES TESTING & SALVAGE Phone: (620) 562-8088

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: B. J. HOPE WitnessType: PARTIAL  
Date/Time Plugging Completed: 01/28/2010 1:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. PERFORATE @ 950', 600', AND 280'. RUN TUBING TO 2900' AND PUMP 40 SX'S CEMENT WITH 100 #'S COTTON HULLS AT 1100 #'S. PULL TUBING TO 950' AND PUMP 35 SX'S CEMENT GETTING CIRCULATION, PULL TUBING TO 600' AND PUMP 35 SX'S CEMENT GETTING CIRCULATION, PULL TUBING 50 280' AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF. CONNECT ON TO SURFACE CASING AND PUMP CEMENT - GOT RETURNS OUT OF CASING. CASING STAYED FULL. USED 190 SX'S CEMENT.

Perfs:

Top	Bot	Thru	Comments
3058	3098	CSG	KANSAS CITY M
2990	2998	CSG	KANSAS CITY K

INVOICED  
DATE 2/24/10  
INV. NO. 2010060777

RECEIVED  
FEB 05 2010  
KCC WICHITA

Remarks: 60-40 POZ, 4% GEL. LOG TECH OF KD TICKET #5948. COPELAND CEMENT TICKET #C-35831.

Plugged through: TBG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

JK