

#129.68

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-20151-00-01
Spot: SENE Sec/Twnshp/Rge: 26-8S-25W
3135 feet from S Section Line, 795 feet from E Section Line
Lease Name: MINIUM Well #: 3
County: GRAHAM Total Vertical Depth: 3990 feet

Operator License No.: 6009
Op Name: DOUBLE EAGLE EXPLORATION, INC.
Address: 800 W 47TH ST STE 318
KANSAS CITY, MO 64112

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	210	0	160 SX
T1	2.375	3867		
DVT		1365		
PKR		3865		
PROD	4.5	3988	0	150 SX

Well Type: EOR UIC Docket No: E24222.1 Date/Time to Plug: 02/02/2010 9:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: HAROLD BELLERIVE Company: DOUBLE EAGLE EXPLORATION, I Phone: (785) 635-4531

Proposed Plugging Method:	Ordered 230 sxs 60/40 pozmix - 4% gel - 400# hulls. Port collar at 1365' - circulated with 400 sxs. 03/23/2009 - Well was plugged back 2012' w/100 sxs 60/40 pozmix - 4% gel - 3% cc.
---------------------------	---

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/02/2010 10:30 AM KCC Agent: PAT BEDORE

Actual Plugging Report:
Ran tubing to 1980' - pumped 90 sxs 60/40 pozmix - 4% gel with 200# hulls.
Pulled tubing to 1000' - pumped 45 sxs 60/40 pozmix - 4% gel to circulate to surface.
Pulled all tubing. Hooked onto 4 1/2" casing - pumped 15 sxs 60/40 pozmix - 4% gel.
S.I.P. 300#.
Hooked to 8 5/8" x 4 1/2" annulus - pumped 15 sxs 60/40 pozmix - 4% gel.
S.I.P. 300#.

Perfs:

Top	Bot	Thru	Comments
3918	3923		

RECEIVED
FEB 12 2010
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #33768.

Plugged through: TBG

INVOICED
DATE 2/24/10
INV. NO. 2010060779

District: 04

Signed Pat Bedore
(TECHNICIAN) CM

FEB 04 2010

CHIEF DRILLING CO., INC. #3 MINIMUM 150'S. C SE NE 26-8-25W

GT. BEND, KS.
 Contr. CO. TOOLS City. GRAHAM

Geol. CO. GEOL Pool HOLLY WEST

E. 2424 KB Cm. 6/5/68 Cp. 7/3/68 IP 91 BOPD N/W
 LANS 3918-23

API 15-065-20,151

LOG Tops	Depth	Datum
ANH	2163	+ 261
HEEB	3720	-1296
TOR	3746	-1322
LANS	3761	-1337
BKC	3981	-1557
LTD	-3990	-1566

Csg. 8" 210/160sx; 4 1/2" 3988/150sx
 DST 3906-25/90" 1230' GIP, 800' CL
 OIL; 120' MO, BHP 990-920#,
 FP 105-310#

CO PF 10/3918-23/ SWB 1 1/2 BOPH
 NATL/3 HRS; FU 950' OIL N/W 12
 HRS; A 500; REC LD, SWB 7 BOPH
 N/W/5 HRS; A 1000; REC LD, SWB
 SWB 7 BOPH N/W 5 HRS; A 1000;
 REC LD; SWB 14 BOPH N/W/6 HRS,
 POP

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS