

* 66.63

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-22286-00-00
Spot: E2NE Sec/Twnshp/Rge: 26-8S-25W
2130 feet from N Section Line, 610 feet from E Section Line
Lease Name: MINIUM Well #: WSW 1
County: GRAHAM Total Vertical Depth: 2050 feet

Operator License No.: 6009
Op Name: DOUBLE EAGLE EXPLORATION, INC.
Address: 800 W 47TH ST STE 318
KANSAS CITY, MO 64112

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	215	0	150 SX
T1	2.375	1732		
PROD	4.5	2037	0	500 SX

Well Type: WSW UIC Docket No: _____ Date/Time to Plug: 02/01/2010 1:00 PM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: HAROLD BELLERIVE Company: DOUBLE EAGLE EXPLORATION, I Phone: (785) 635-4531

Proposed Plugging Method: Ordered 230 sxs 60/40 pozmix - 4% gel - 400# hulls.
Perf at 1360' and 200'.

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/01/2010 3:20 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 1780' - pumped 50 sxs 60/40 pozmix - 4% gel with 200# hulls.
Pulled tubing to 1000' - pumped 70 sxs 60/40 pozmix - 4% gel with 200# hulls to circulate to surface.
Pulled all tubing. Hooked onto 4 1/2" casing - pumped 10 sxs 60/40 pozmix - 4% gel.
S.I.P. 350#.
Hooked onto 8 5/8" x 4 1/2" annulus - pumped 5 sxs 60/40 pozmix - 4% gel.
S.I.P. 350#.

Perfs:

Top	Bot	Thru	Comments
1870	1920		
1820	1870		

Remarks: ALLIED CEMENTING COMPANY-TICKET #33766.

Plugged through: TBG

INVOICED
DATE 2/24/10
INV. NO. 2010060779

RECEIVED
FEB 12 2010

KCC WICHITA

District: 04

Signed Pat Bedore
(TECHNICIAN)

cm

CHIEF DRILLING
WICHITA KS 67202

26-08S-25W
2130'FNL & 610'FEL, SEC

1 MINIMUM WSW

site: 3/4 S OF MORLAND KS
contr: WARRIOR DRILLING

cty: GRAHAM
field: HOLLEY WEST

API 15-065-22286

			▲

geol:
tr date 12/23/85 spd date 12/28/85 drig comp 12/29/85 card issued 07/03/86 last revised 10/30/95

ELV: 2424 KB, 2419 GL
tops.....depth/ datum
RTD2050 + 374
NO TOPS RPTD

IP status
WSW, CED HILL 1820-1920 OA, 06/26/86
CORR: 10/30/95 - ORIG FR IN C E/2 NE
NOTE: INFO REL 11/13/86 - WAS WSW - TIGHT HOLE
CSG: 8-5/8" 215 / 150 SX, 4-1/2" 2037 / 500 SX
NO CORES OR DSTS
MICT - CO, PF (CED HILL) 1870-1920, 1820-1870, WSW -
DAILY RATE NA, 6/26/86