

140.99

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-22582-00-00
Spot: W2E2SW Sec/Twnshp/Rge: 17-14S-22W
1310 feet from S Section Line, 3540 feet from E Section Line
Lease Name: JOANN Well #: 1-17
County: TREGO Total Vertical Depth: 4338 feet

Operator License No.: 30717
Op Name: DOWNING-NELSON OIL CO INC
Address: PO BOX 372
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	222	0	150 SX CMT
T1	2.375	4093		
PC		1675		125 SX CMT
PROD	5.5	4338	0	325 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/26/2010 10:00 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: TERRY W. PIESKER Company: DOWNING-NELSON OIL CO., INC. Phone: (785) 735-4363

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 300# hulls - 15 sxs gel.
Port collar at 1675' w/125 sxs.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/26/2010 11:15 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:
Backside full.
Tied on the 5 1/2" - pumped 75 sxs cement w/300# hulls - followed with 15 sxs gel - followed with 200 sxs cement.
Full.

Perfs:

Top	Bot	Thru	Comments
4170	4173		
4150	4152		
4143	4145		
4128	4130		
4109	4111		
4033	4036		

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 01 2010
CONSERVATION DIVISION
WICHITA, KS

INVOICED
DATE 2/24/10
INV. NO. 2010060781

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #3536.
Plugged through: CSG

District: 04 Signed [Signature]
(TECHNICIAN) CM

JAN 28 2010

Replacement Card

DOWNING-NELSON OIL CO
HAYS KS 67601-0372

17-14S-22W
1310'FSL & 1740'FWL, SEC
KANSAS

#1-17 RIES, JO ANN

City: TREGO

Spot: NE NW SE SW API 15-195-22582

Site: 10-3/4 S & 3 W OF OGALLAH KS

Lat/Long: 38.83055 -99.79413

Field: CEDAR BLUFF EXT (3/4 N; REVIVAL)

OIL

FR: 09/24/2008 Spd: 09/30/2008 Drig Cp: 10/06/2008 Issued: 03/16/2009 Revised: 08/31/2009

Copyright 2009 Independent Oil & Gas Service, Inc. Wichita, KS

Side 1

IP Status:

**OIL, P 5 BO & 10 BWPD, MARM 4033-4111 OA, CHER
4128-4173 OA, (NEW PAY), 12/10/2008**

Revisions: CORR & INFO REL: 8/31/2009 - CORR ELEV
(WAS 2267 KB, 2259 GL); ADDED DST

Contr: DISCOVERY DRILLING #1

Geol: RON NELSON

Elev: 2268 KB, 2260 GL, 2266 DF

Formation Tops: (L-Log, S-Sample, D-Driller)

L ANH	1696 +572
L B/ANH	1736 +532
L TOP	3402 -1134
L HEEB	3641 -1373
L TOR	3658 -1390
L LANS	3674 -1406
L BKC	3928 -1660
L MARM	4032 -1764
L CHER SH	4118 -1850
L CHER SD	4170 -1902

L MISS	4212 -1944
LTD	4338 -2070
RTD	4338 -2070

Csg: 8-5/8" 222 / 150 SX (ALT 2), 5-1/2" 4338 / 325 SX,
PORT COLLAR AT 1675 / 125 SX

Find:

COMMENT: PROPOSED START 10/6/2008; MI &
RURT 9/30/2008

NO CORES

DST(1) 4080-4180 (FT SC, CHER) 45-45-45-45,
REC 250' TF: 60' M, 60' OCM (95% M, 5% OIL), 60'
OCM (80% M, 20% OIL), 70' GSY OCM (65% M,
30% OIL, 5% G) ISIP 1210# FSIP 1184# IFP
54#-115# / FFP 116#-169# IHP 2082# FHP 2027#
BHT 120°

Comp Info: TRGT ZN: LKC, CHER (OIL), PTD 4150
(ARB), MICT - CO, PF (MARM) 4033-4036,
4109-4111, (CHER) 4128-4130, 4143-4145,
4150-4152, 4170-4173, W / 4 SPF, ISOLATED PFS