

# 135.20

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-195-22287-00-00  
Spot: SWNENW Sec/Twnshp/Rge: 9-14S-21W  
4370 feet from S Section Line, 3770 feet from E Section Line  
Lease Name: ERWIN KROEGER Well #: 1-9  
County: TREGO Total Vertical Depth: 4160 feet

Operator License No.: 30717  
Op Name: DOWNING-NELSON OIL CO INC  
Address: PO BOX 372  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	222	0	150 SX CMT COMMON 2% GEL, 3% CC
T1	2.375	3895		
DVT		1623		165 SX CMT
PROD	5.5	4156	0	150 SX CMT EA-2

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/26/2010 9:00 AM  
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING  
Proposal Rcvd. from: TERRY W. PIESKER Company: DOWNING-NELSON OIL CO., INC. Phone: (785) 735-4363

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 300# hulls - 15 sxs gel.  
DV Tool at 1623' w/165 sxs.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/26/2010 10:15 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Backside full.  
Tied onto 5 1/2" - pumped 75 sxs cement with 300# hulls - followed with 15 sxs gel - followed with 225 sxs cement.  
Shut in 150# P.S.I.

Perfs:

Top	Bot	Thru	Comments
4092	4095		
4078	4081		
4062	4064		
4050	4053		
3782	3788		
3761	3763		
3656	3660		

RECEIVED  
KANSAS CORPORATION COMMISSION  
FEB 01 2010  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #3534.

Plugged through: CSG

INVOICED  
DATE 2/24/10  
INV. NO. 200060781

District: 04

Signed [Signature]  
(TECHNICIAN) CM

JAN 28 2010

DOWNING-NELSON OIL CO  
HAYS KS 67601

9-14S-21W  
910' FNL & 1510' FWL, SEC

#1-9 KROEGER, ERWIN

site 5 S & 5-1/4 W OF ELLIS KS  
 contr: DISCOVERY DRILLING #2  
 geol: RON NELSON  
 fr date 02/15/2005 spd date 05/24/2005 drlg comp 05/30/2005  
 cy: TREGO field: MADDEN NORTH EXT (1/2+ N; INFLD DISC)  
 API 15-195-22287  
 card issued 10/10/2005 last revised 12/19/2005


ELV: 2269 KB, 2261 GL LOG  
 tops.....depth/datum  
 ANH.....1650 +619  
 B/ANH.....1696 +573  
 TOP.....3351 -1082  
 HEEB.....3588 -1319  
 TOR.....3606 -1337  
 LANS.....3624 -1355  
 BKC.....3866 -1597  
 MARM.....3960 -1691  
 RTD.....4160 -1891

IP status  
 OIL, P 5 BO & 15 BWP, LKC 3656-3788 OA, MARM  
 4050-4095 OA, (NEW PAY), 07/10/2005  
 INFO RELEASED: 12/19/2005 - WAS OIL WELL - TIGHT  
 HOLE  
 CSG: 8-5/8" 221.9 / 150 SX (ALT 2), 5-1/2" 4155.75 / 150 SX,  
 MULTI STAGE COLLAR AT 1623 / 165 SX  
 NO CORES  
 DSTS TAKEN - DETAILS NA  
 TRGT ZN: LKC, ARB (OIL), PTD 4100 (ARB), MICT  
 (5/31/2005) - CO, PF (MARM) 4078-4081, 4092-4095, W / 4  
 SPD, AC 500 GAL (7.5% MA), SWB LD, SO, PF (MARM)  
 4050-4053, 4062-4064, W / 4 SPF, AC 750 GAL (15% MA), SWB  
 LD, SO, PF (LANS H) 3761-3763, (LANS I) 3782-3788, W / 4  
 SPF, AC 2000 GAL (15% NE), SWB LD, SO, PF (LANS C)

COPYRIGHT 2006  
 INDEPENDENT OIL & GAS SERVICE, INC.  
 WICHITA, KANSAS

(over)