

133.25

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-22163-00-00
Spot: N2NW Sec/Twnshp/Rge: 5-14S-21W
4545 feet from S Section Line, 3960 feet from E Section Line
Lease Name: LOCKER A Well #: 1
County: TREGO Total Vertical Depth: 4100 feet

Operator License No.: 30717
Op Name: DOWNING-NELSON OIL CO INC
Address: PO BOX 372
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	220	0	135 SX
PROD	5.5	4098	0	150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/26/2010 1:00 PM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: TERRY W. PIESKER Company: DOWNING-NELSON OIL CO., INC. Phone: (785) 735-4363

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 300# hulls - 15 sxs gel.
Port collar at 1637' w/200 sxs.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/26/2010 3:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Backside full.
Tied onto the 5 1/2" - pumped 75 sxs cement with 300# hulls - followed with 15 sxs gel - followed with 155 sxs cement.
Shut in at 1500# P.S.I.

Perfs:

Top	Bot	Thru	Comments
4040	4044		
4022	4026		

RECEIVED
KANSAS CORPORATION COMMISSION

FEB 01 2010

CONSERVATION DIVISION
WICHITA, KS

INVOICED

DATE 2/24/10

INV. NO. 2010060781

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET 33535.

Plugged through: CSG

District: 04

Signed _____

CM - Mills

(TECHNICIAN)

CM

DOWNING-NELSON OIL CO
HAYS KS 67601

5-14S-21W
75'S, C N/2 NW

1 LOCKER A

site: 8-1/4 S & 2-1/2 E OF OGALLAH KS
contr: DISCOVERY DRILLING # 1
geol: RON NELSON

cty: TREGO
field: LOCKER

API 15-195-22163

tr date 11/02/95 spd date 11/24/95 drlg comp 11/30/95 card issued 03/04/96 last revised 03/04/96

ELV: 2265 KB, 2257 GL LOG	
tops.....	depth/ datum
ANH.....	1660 + 605
B/ANH.....	1702 + 563
TOP.....	3348 -1083
HEEB.....	3584 -1319
TOR.....	3604 -1339
LANS.....	3620 -1355
BKC.....	3866 -1601
MARM.....	3962 -1697
CHER SH.....	4008 -1743
CHER SD A.....	4022 -1757
CHER SD C.....	4040 -1775
LTD.....	4100 -1835
RTD.....	4100 -1835

IP status:
OIL, P 20 BOPD, NW, CHER 4040-4044 , 01/03/96
 CSG: 8-5/8" 219.81 (ALT 2), 5-1/2" 4098, PORT COLLAR AT 1637 / 200 SX
 NO CORES
 DST (1) 3998-4050 (CHER SD A-C), / 30-45-30-45, (1ST OP) BLO TO BTM BKT/7", ISI: BLED OFF, BLEW BK/1", WK SURF BLO, (2ND OP) BLO TO BTM BKT/8.5", FSI: BLED OFF, BLEW BK/2.5", WK SURF BLO, 300' GIP, REC 140' GSY OIL (10% G, 90% OIL), 280' GSY MDY OIL (20% G, 60% OIL, 20% M) ISIP 1133# FSIP 1096# IFP 120# -174# FFP 185# -207# IHP 2065# FHP 2032#
 TRGT ZN: CHER, PTD 4100 (CHER), MICT - CO, PF (CHER SD) 4040-4044, W / 4 SPF, GSO, NAT, SET 2-7/8" TBG AT 4065, NO PKR, POP, P 20 BOPD, NW (GR 39.5), 1/3/96

COPYRIGHT 1996
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS