

\$40.63

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-019-19707-00-00  
Spot: NESENE SW Sec/Twnshp/Rge: 22-34S-11E  
1728 feet from S Section Line, 2933 feet from E Section Line  
Lease Name: WHITE Well #: 16  
County: CHAUTAUQUA Total Vertical Depth: 1250 feet

Operator License No.: 7155  
Op Name: FARRIS, BILL  
Address: 888 STATE HWY 99  
SEDAN, KS 67361

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/19/2010 3:00 PM  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.

Proposal Rcvd. from: \_\_\_\_\_ Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed Plugging Method: Perforate at 700' and 350'. 50' plug at TD (1250), 50' plug at 700' and 350' to surface.

Plugging Proposal Received By: DUANE SIMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/20/2010 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Contractor ran 1" to 1250' gelled hole and spotted 10 sack plug. Pulled 1" out and perforated well at 700' and 350'. Next day ran 1" to 700' and spotted 10 sacks of cement. Pulled 1" up to 350' and circulated cement to surface. Pulled 1" and topped well off. A total of 177 sacks of cement were used to plug this well.

RECEIVED

FEB 9 2010 DAS

KCC Chanute Dist. #3

INVOICED

DATE 2/25/10

INV. NO. 2810060786

RECEIVED

FEB 18 2010


KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)