

State of Kansas



FORM - CP-2  
Rev. 9-8-64

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission  
CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

15-195-20053-00-00

RECEIVED  
CONSERVATION COMMISSION  
DEC 8 1967  
12-08-1967  
CONSERVATION DIVISION  
WICHITA, KANSAS

Dear Sir:

Mr. Bob Miller of L. J. Dreiling & Sons, Inc., has this  
date requested permission to plug the following described well:

Mr. Miller guarantees payment of the plugging fee.

Operator's full Name: Beacon Resources Corporation,

Complete Address: 412 Union Center, Wichita, Kansas.

Lease Name: Hubalek Well No. 1

Location: NW-SW-SE Sec. 19 Twp. 12 Rge. (E)(W) 22

County Trego Total Depth 3470 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Miller was instructed to plug the well as follows:

160'--8 5/8" Surface pipe, cement circulated with 125 Sx.  
Dakota section from 1310' to 1535'.

Circulate hole with heavy mud. Pull DP to 1550' and displace 100 Sx.  
cement thru DP. Pull DP to 180' and displace 20 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with  $\frac{1}{2}$  sack hulls and 10 Sx. cement to  
bottom of cellar.

Very truly yours,

H. D. Nichols

Conservation Division Agent