

State of Kansas



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. James Brown of Tenneco Oil Co. has this date requested permission to plug the following described well:

Operator's Full Name: Tenneco Oil Co.

Complete Address: 139 Ciudad Bldg. 3000 United Founders Blvd. Oklahoma City OK 73104

Lease Name: Elmer Tract Well No. 11-4

Location: CSE NW NW Sec. 10 Twp. 10 Rge. 25 (E) (W)

County: Shawnee Total Depth: 4268'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Brown was instructed to plug the well as follows:

8 5/8 @ 208' w/130 sv - 5 1/2" @ 4265' w/200 sv. Csg.
perched @ 2019' - Ran tubing to 4000' + pumped 100 sv
common cement for bottom plug - Rec approx 1400' csg.
Ordered 140 sv 50/50 permix 6% gel - 3% cc + 28 gel - 6
hulls + 8 5/8" plug. Pumped in 5 hulls -> 14 gel. -> 1 hull ->
70 cement -> 14 gel. -> Rel plug -> 70 cement.

Very truly yours,

Dennis L. Jamel
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION
AUG 09 1982
CONSERVATION DIVISION
Wichita, Kansas