

State of Kansas



ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Bob Barnes of Barnes & Sons Pipe Pulling Co. has this date requested permission to plug the following described well:

Mr. Barnes guarantees payment of the plugging fee.

Operator's full Name: Empire Drilling Company,

Complete Address: 650 4th National Bank Building, Wichita, Kansas.

Lease Name: M. Dinkel Well No. 1

Location: NW-NW-SW Sec. 15 Twp. 10 Rge. (E)(W) 25

County: Graham Total Depth 4205' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Barnes was instructed to plug the well as follows:

195'--8 5/8" Surface casing, cement circulated with 200 Sx.

3975'--5 1/2" Production casing cemented with 75 Sx. Well plugged back to 3964'. Top perforations @ 3734'. Dakota section top @ 950'.

Sand well back to 3700' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 35 sacks gel plus 5 sacks hulls and 130 Sx. cement staged.

RECEIVED
STATE CORPORATION COMMISSION

OCT 8 - 1968

CONSERVATION DIVISION
Wichita, Kansas

Very truly yours,

W. S. Feheli

Conservation Division Agent