



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

15-195-00857-00-00

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUL 28 1969
07-28-1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Phil Lesseig of Pan-American Petr., Corp., has this date requested permission to plug the following described well:

Mr. Lesseig guarantees payment of the plugging fee.

Operator's full Name: Pan American Petroleum Corporation,

Complete Address: P. O. Box #432, Liberal, Kansas.

Lease Name: R. M. Anderson Well No. C-1

Location: NE-NE-NE Sec. 34 Twp. 12 Rge. (E)(W) 22

County: Trego Total Depth 4065' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Lesseig was instructed to plug the well as follows:

199'--8 5/8" Surface casing, cement circulated with 150 Sx.
4064'--5 1/2" Production casing cemented on bottom with 300 Sx. DV tool set @ 1761' with 800 Sx, cement circulated. Bridge plug @ 3978'. Top perforations @ 3588'. Well plugged back to 3910'.

Run tubing to bottom and displace 75 Sx, cement thru tubing. Pull tubing to 3500' and displace 35 Sx, gel thru tubing, pull tubing to 900' and displace 50 Sx, cement, pull tubing to 500' and displace 6 Sx, gel. Pull tubing and fill to bottom of cellar w/cement.

Very truly yours,

M. L. Nichols
Conservation Division Agent