

3/13/10

ORIGINAL

Form ACO-1  
October 2008  
Form Must Be Typed

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION

**CONFIDENTIAL**

**WELL COMPLETION FORM**  
WELL HISTORY - DESCRIPTION OF WELL & LEASE

OPERATOR: License # 5363  
Name: Berexco Inc.  
Address 1: PO Box 20380  
Address 2: \_\_\_\_\_  
City: Wichita State: KS Zip: 67208  
Contact Person: Jeremy Ensz  
Phone: (316) 265-3311  
CONTRACTOR: License # 5147  
Name: Beredco Inc.  
Wellsite Geologist: Bryan Bynog  
Purchaser: Central Crude Corporation

Designate Type of Completion:  
 New Well  Re-Entry  Workover  
 Oil  SWD  SIOW  
 Gas  ENHR  SIGW  
 CM (Coal Bed Methane)  Temp. Abd.  
 Dry  Other \_\_\_\_\_  
(Core, WSW, Expl., Cathodic, etc.)

If Workover/Re-entry: Old Well Info as follows:  
Operator: \_\_\_\_\_  
Well Name: \_\_\_\_\_  
Original Comp. Date: \_\_\_\_\_ Original Total Depth: \_\_\_\_\_  
 Deepening  Re-perf.  Conv. to Enhr.  Conv. to SWD  
 Plug Back: \_\_\_\_\_ Plug Back Total Depth \_\_\_\_\_  
 Commingled Docket No.: \_\_\_\_\_  
 Dual Completion Docket No.: \_\_\_\_\_  
 Other (SWD or Enhr.?) Docket No.: \_\_\_\_\_  

1/28/09	2/8/09	3/5/09
Spud Date or Recompletion Date	Date Reached TD	Completion Date or Recompletion Date


API No. 15 - 171-20713-0000  
Spot Description: \_\_\_\_\_  
NE NW Sec. 36 Twp. 16 S. R. 32  East  West  
660 Feet from  North /  South Line of Section  
1990 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Scott  
Lease Name: Joyce Well #: 1  
Field Name: N/A  
Producing Formation: Johnson  
Elevation: Ground: 2963 Kelly Bushing: 2976  
Total Depth: 4756 Plug Back Total Depth: 4711  
Amount of Surface Pipe Set and Cemented at: 328 Feet  
Multiple Stage Cementing Collar Used?  Yes  No  
If yes, show depth set: 2357 Feet  
If Alternate II completion, cement circulated from: 2357  
feet depth to: surface w/ 450 sx cmt.

Drilling Fluid Management Plan ART #103-14-09  
(Data must be collected from the Reserve Pit)  
Chloride content: 2900 ppm Fluid volume: 1200 bbls  
Dewatering method used: Evaporation  
Location of fluid disposal if hauled offsite: \_\_\_\_\_  
Operator Name: \_\_\_\_\_  
Lease Name: \_\_\_\_\_ License No.: \_\_\_\_\_  
Quarter \_\_\_\_\_ Sec. \_\_\_\_\_ Twp. \_\_\_\_\_ S. R. \_\_\_\_\_  East  West  
County: \_\_\_\_\_ Docket No.: \_\_\_\_\_

**INSTRUCTIONS:** An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: \_\_\_\_\_  
Title: District Engineer Date: 3/13/09  
Subscribed and sworn to before me this 13th day of March  
20 09  
Notary Public: Anne Bowman  
Date Commission Expires: 6/2/11



**KCC Office Use ONLY**  
 Letter of Confidentiality Received  
If Denied, Yes  Date: \_\_\_\_\_  
 Wireline Log Received  
 Geologist Report Received  
 UIC Distribution

Operator Name: Berexco Inc. Lease Name: Joyce Well #: 1  
 Sec. 36 Twp. 16 S. R. 32  East  West County: Scott **MAR 13 2009**

**CONFIDENTIAL**

**INSTRUCTIONS:** Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <i>(Attach Additional Sheets)</i>  Samples Sent to Geological Survey <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Cores Taken <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Electric Log Run <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <i>(Submit Copy)</i>  List All E. Logs Run: <b>DIL, CNL/CDL, MEL, BHCS</b>	<input checked="" type="checkbox"/> Log Formation (Top), Depth and Datum <input type="checkbox"/> Sample  <table style="width:100%; border-collapse: collapse;"> <tr> <td style="width:70%;">Name</td> <td style="width:15%;">Top</td> <td style="width:15%;">Datum</td> </tr> <tr> <td>Base Anhy</td> <td>2375</td> <td>+601</td> </tr> <tr> <td>Heebner</td> <td>3941</td> <td>-965</td> </tr> <tr> <td>LKC</td> <td>3978</td> <td>-1002</td> </tr> <tr> <td>Ft. Scott</td> <td>4508</td> <td>-1532</td> </tr> <tr> <td>Johnson</td> <td>4572</td> <td>-1596</td> </tr> <tr> <td>Mississippi</td> <td>4637</td> <td>-1661</td> </tr> </table>	Name	Top	Datum	Base Anhy	2375	+601	Heebner	3941	-965	LKC	3978	-1002	Ft. Scott	4508	-1532	Johnson	4572	-1596	Mississippi	4637	-1661
Name	Top	Datum																				
Base Anhy	2375	+601																				
Heebner	3941	-965																				
LKC	3978	-1002																				
Ft. Scott	4508	-1532																				
Johnson	4572	-1596																				
Mississippi	4637	-1661																				

CASING RECORD <input checked="" type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface	12-1/4"	8-5/8"	20	328	See Attached	300	See Attached
Production	7-7/8"	5-1/2"	14	4756	See Attached	675	See Attached

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate <input type="checkbox"/> Protect Casing <input type="checkbox"/> Plug Back TD <input type="checkbox"/> Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
4	4597-4602 Johnson	1000 gal 15% NEFE	4597-4602
		<b>RECEIVED</b>	
		<b>MAR 17 2009</b>	
		<b>KCC WICHITA</b>	

TUBING RECORD: Size: <u>2-3/8</u> Set At: <u>4701</u> Packer At: <u>N/A</u>		Liner Run: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
Date of First, Resumed Production, SWD or Enhr. <u>3/9/09</u>		Producing Method: <input type="checkbox"/> Flowing <input checked="" type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain)
Estimated Production Per 24 Hours	Oil Bbls. <u>20</u>	Gas Mcf <u>0</u> Water Bbls. <u>0</u> Gas-Oil Ratio Gravity

DISPOSITION OF GAS: <input type="checkbox"/> Vented <input type="checkbox"/> Sold <input type="checkbox"/> Used on Lease <i>(If vented, Submit ACO-18.)</i>	METHOD OF COMPLETION: <input type="checkbox"/> Open Hole <input checked="" type="checkbox"/> Perf. <input type="checkbox"/> Dually Comp. <input type="checkbox"/> Commingled <input type="checkbox"/> Other (Specify) _____	PRODUCTION INTERVAL: <u>Johnson 4597-4602</u>
---	---	--

# ALLIED CEMENTING CO., LLC. 044209

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:  
Oakley

DATE <u>1-28-09</u>	SEC. <u>36</u>	TWP. <u>16s</u>	RANGE <u>32w</u>	CALLED OUT	ON LOCATION <u>3:00pm</u>	JOB START <u>6:30pm</u>	JOB FINISH <u>7:00pm</u>
LEASEE <u>Joyce</u>	WELL # <u>1</u>	LOCATION <u>scott city 8N 6E 1N</u>		COUNTY <u>SCOTT</u>	STATE <u>KS</u>		
OLD OR <u>NEW</u> (Circle one)		<u>1w 3/4N E into</u>					

CONTRACTOR Beredco Rig 2  
 TYPE OF JOB Surface  
 HOLE SIZE 12 1/4 T.D. 328'  
 CASING SIZE 8 5/8 DEPTH 328'  
 TUBING SIZE DEPTH  
 DRILL PIPE DEPTH  
 TOOL DEPTH  
 PRES. MAX MINIMUM  
 MEAS. LINE SHOE JOINT  
 CEMENT LEFT IN CSG. 15'  
 PERFS.  
 DISPLACEMENT 19.93 BBL

OWNER same  
 CEMENT  
 AMOUNT ORDERED 200 SKS 6 3/4 2 1/2 gel 30 cc

COMMON	<u>120 SKS</u>	@	<u>15.45</u>	<u>1854.00</u>
POZMIX	<u>80 SKS</u>	@	<u>8.00</u>	<u>640.00</u>
GEL	<u>4 SKS</u>	@	<u>20.80</u>	<u>83.20</u>
CHLORIDE	<u>6 SKS</u>	@	<u>58.20</u>	<u>349.20</u>
ASC		@		

EQUIPMENT  
 PUMP TRUCK CEMENTER Andrew  
 # 423-281 HELPER Larene  
 BULK TRUCK  
 # 347 DRIVER Darrin  
 BULK TRUCK  
 # DRIVER

RECEIVED  
MAR 17 2009

HANDLING	<u>210 SKS</u>	@	<u>2.40</u>	<u>504.00</u>
MILEAGE	<u>10 1/2 sk/mile</u>			<u>1365.00</u>
				TOTAL <u>4795.40</u>

REMARKS: **KCC WICHITA**

Cement in cellar.  
  
  
  
  
  
  
  
  
  
Thank you

CHARGE TO: BereXCO  
 STREET \_\_\_\_\_  
 CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

**SERVICE**

DEPTH OF JOB	<u>328'</u>		
PUMP TRUCK CHARGE			<u>1018.00</u>
EXTRA FOOTAGE		@	
MILEAGE	<u>6.5 miles</u>	@	<u>7.00</u> <u>455.00</u>
MANIFOLD	<u>head rental</u>	@	<u>113.00</u>

TOTAL 1586.00

**PLUG & FLOAT EQUIPMENT**

<u>8 5/8</u>	<u>1 surface plug</u>	@	<u>68.00</u>
		@	
		@	
		@	
		@	

TOTAL 68.00

To Allied Cementing Co., LLC.  
 You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PRINTED NAME Bruce A. Walcott  
 SIGNATURE B Walcott

SALES TAX (If Any) \_\_\_\_\_  
 TOTAL CHARGES \_\_\_\_\_  
 DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS

# ALLIED CEMENTING CO., LLC. 044211

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT: Oakley

DATE <u>1-29-09</u>	SEC. <u>36</u>	TWP. <u>16s</u>	RANGE <u>32w</u>	CALLED OUT	ON LOCATION <u>10:30am</u>	JOB START <u>12:00pm</u>	JOB FINISH <u>12:30pm</u>
LEASE <u>Joyce</u>	WELL # <u>1</u>	LOCATION <u>scott city 8NLE IN 1W</u>			COUNTY <u>scott</u>	STATE <u>KS</u>	
OLD OR <input checked="" type="radio"/> NEW (Circle one)				<u>3/4" E into</u>			

CONTRACTOR Beredco Rig 2  
 TYPE OF JOB 1 inch  
 HOLE SIZE 12 1/4 T.D. 328'  
 CASING SIZE 8 5/8 DEPTH 328'  
 TUBING SIZE \_\_\_\_\_ DEPTH \_\_\_\_\_  
 DRILL PIPE \_\_\_\_\_ DEPTH \_\_\_\_\_  
 TOOL \_\_\_\_\_ DEPTH \_\_\_\_\_  
 PRES. MAX \_\_\_\_\_ MINIMUM \_\_\_\_\_  
 MEAS. LINE \_\_\_\_\_ SHOE JOINT \_\_\_\_\_  
 CEMENT LEFT IN CSG. \_\_\_\_\_  
 PERFS. \_\_\_\_\_  
 DISPLACEMENT \_\_\_\_\_

**EQUIPMENT**

PUMP TRUCK CEMENTER Andrew  
 # 423-281 HELPER Larone  
 BULK TRUCK  
 # 377 DRIVER Darrin  
 BULK TRUCK  
 # \_\_\_\_\_ DRIVER \_\_\_\_\_

**REMARKS:**  
Mix 100 sks thru 1 inch from  
20' TO surface.  
Cement did come TO  
surface

*Thank you*

CHARGE TO: Berexco  
 STREET \_\_\_\_\_  
 CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

To Allied Cementing Co., LLC.  
 You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PRINTED NAME Bruce A. Woldery  
 SIGNATURE [Signature]

OWNER same  
 CEMENT  
 AMOUNT ORDERED 100 sks com 36cc

COMMON <u>100 sks</u>	@	<u>15.45</u>	<u>1545.00</u>
POZMIX _____	@		
GEL _____	@		
CHLORIDE <u>3 sks</u>	@	<u>58.20</u>	<u>174.60</u>
ASC _____	@		

HANDLING <u>103 sks</u>	@	<u>2.40</u>	<u>247.20</u>
MILEAGE <u>10 1/2 sk/mile</u>			<u>668.50</u>
TOTAL			<u>2636.30</u>

**SERVICE**

DEPTH OF JOB 20'  
 PUMP TRUCK CHARGE \_\_\_\_\_ 1018.00  
 EXTRA FOOTAGE \_\_\_\_\_ @ \_\_\_\_\_  
 MILEAGE 65 miles @ 7.00 455.00  
 MANIFOLD \_\_\_\_\_ @ \_\_\_\_\_  
 \_\_\_\_\_ @ \_\_\_\_\_

**RECEIVED**  
**MAR 17 2009**  
 TOTAL 1423.00

**KCC WICHITA**

**PLUG & FLOAT EQUIPMENT**

_____	@	_____
_____	@	_____
_____	@	_____
_____	@	_____
_____	@	_____

TOTAL \_\_\_\_\_  
 SALES TAX (If Any) \_\_\_\_\_  
 TOTAL CHARGES \_\_\_\_\_  
 DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS

# ALLIED CEMENTING CO., LLC. 044010

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT: OAKLEY, KS

DATE <u>2-9-09</u>	SEC. <u>36</u>	TWP. <u>16S</u>	RANGE <u>32W</u>	CALLED OUT	ON LOCATION <u>3:30pm</u>	JOB START <u>1:30am</u>	JOB FINISH <u>2:30am</u>
LEASE <u>Soyce</u>	WELL# <u>#1</u>	LOCATION <u>83 + Hwy 4-66-1W</u>			COUNTY <u>Scott</u>	STATE <u>KS</u>	
OLD OR NEW (Circle one)		<u>1-W - 3/4 W E/W</u>					

CONTRACTOR Beredco #2 OWNER KCC

TYPE OF JOB 2-Stage (Bottom) MAR 13 2009

HOLE SIZE 7 7/8 T.D. 4760'

CASING SIZE 5 1/2 14# DEPTH 4760'

TUBING SIZE DEPTH

DRILL PIPE DEPTH

TOOL DU Tool DEPTH 2354'

PRES. MAX MINIMUM

MEAS. LINE SHOE JOINT 39.50

CEMENT LEFT IN CSG. 39.50

PERFS.

DISPLACEMENT 115.32

CEMENT **CONFIDENTIAL**

AMOUNT ORDERED 755Ks 114#

10-seal - 150SKs ASC 29.00

1090 salt

COMMON	@		
POZMIX	@		
GEL		<u>3</u>	@ <u>20.00</u> <u>62.00</u>
CHLORIDE	@		
ASC		<u>150</u>	@ <u>18.60</u> <u>2790.00</u>
	@		
Salt		<u>17</u>	@ <u>23.95</u> <u>407.15</u>
	@		
10-seal		<u>19#</u>	@ <u>2.50</u> <u>47.50</u>
	@		
Lite		<u>75SKs</u>	@ <u>14.05</u> <u>1053.75</u>
	@		
	@		
HANDLING		<u>259</u>	@ <u>2.45</u> <u>621.55</u>
MILEAGE		<u>1085K+mile</u>	<u>1036.00</u>
			TOTAL <u>6018.40</u>

**EQUIPMENT**

PUMP TRUCK CEMENTER Fuzz Y

# 431 HELPER Kelly

BULK TRUCK

# 373 DRIVER Alvin

BULK TRUCK

# 394 DRIVER Wilbur

**REMARKS:**

Mix 75SKs Lite 114# 10-seal

Tool with 150SKs ASC 29.00 seal 1090

salt. Washout pump & lines.

Displace plus to hatch down,

gent L. & 1500K hand flat held

Drop DU Bomb unit 15min. open DU

Tool @ 1200# zinc for 2 hrs

Job complete @ 2:30am

Thanks Fuzz Y crew

**SERVICE**

DEPTH OF JOB 4766

PUMP TRUCK CHARGE 2185.00

EXTRA FOOTAGE @

MILEAGE 40 @ 7.00 280.00

MANIFOLD + thread @ 113.00

@

@

CHARGE TO: Bereyco Inc.

STREET \_\_\_\_\_

CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

**RECEIVED**

**MAR 17 2009**

TOTAL 2578.00

**KCC WICHITA RUG & FLOAT EQUIPMENT**

1- AFU Float shoe 529.00

1- Hatchdown Assy @ (L) 462.00

1- DU Tool @ (L) 4500.00

5- Baskets @ 186.00 930.00

11- Centralizers @ 57.00 627.00

@

TOTAL 7048.00

To Allied Cementing Co., LLC.

You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PRINTED NAME \_\_\_\_\_

SIGNATURE mal 2

SALES TAX (If Any) \_\_\_\_\_

TOTAL CHARGES \_\_\_\_\_

DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS

12764.94

# ALLIED CEMENTING CO., LLC. 044011

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT: Oakley KS

DATE <u>2-9-09</u>	SEC. <u>36</u>	TWP. <u>16s</u>	RANGE <u>32w</u>	CALLED OUT	ON LOCATION <u>3:30pm</u>	JOB START <u>4:30am</u>	JOB FINISH <u>5:30am</u>
LEASE <u>Joyce</u>	WELL# <u>1</u>	LOCATION <u>83+4 Hwy 5 - 6 E - 1 W</u>			COUNTY <u>Scott</u>	STATE <u>KS</u>	
OLD OR <u>NEW</u> (Circle one)			<u>1w-31w 64</u>				

CONTRACTOR Beredco #2

TYPE OF JOB 2-stage (Top)

HOLE SIZE 7 7/8 T.D. 4760'

CASING SIZE 5 1/2 14\* DEPTH 2354'

TUBING SIZE DEPTH

DRILL PIPE DEPTH

TOOL DU Tool DEPTH 2354'

PRES. MAX MINIMUM

MEAS. LINE SHOE JOINT

CEMENT LEFT IN CSG.

PERFS.

DISPLACEMENT 57.4

**EQUIPMENT**

PUMP TRUCK CEMENTER Fuzzy

# 431 HELPER Kelly

BULK TRUCK

# 373 DRIVER Alvin

BULK TRUCK

# 394 DRIVER Wilbur

**REMARKS:**

Mix 10 sacks in MA - 15 sacks in RH

Mix 400 sacks 1/4" #10 seal Tail

with 50 sacks ASC 2" seal 1090 salt

washed pump & lines. Displace plus

to DU Tool Close tool @ 1600#

hid press 900# cement did

circulate plus down @ 5:30am

Thanks Fuzzy & crew

approx 65 FBTS

CHARGE TO: Beredco Inc

STREET \_\_\_\_\_

CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

To Allied Cementing Co., LLC.

You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PRINTED NAME \_\_\_\_\_

SIGNATURE Mah

OWNER \_\_\_\_\_

CEMENT

AMOUNT ORDERED 450 hide #1/4"

Closeal - 50 ASC 1090 salt

290 seal (used 400 hide)

**KCC**

COMMON \_\_\_\_\_

POZMIX MAR 13 2009

GEL \_\_\_\_\_

CHLORIDE **CONFIDENTIAL**

ASC 50 @ 18.00 = 930.00

hide 400 @ 14.05 = 5620.00

Salt 6 @ 23.95 = 143.70

Closeal 100\* @ 2.50 = 250.00

HANDLING 491 @ 2.40 = 1178.40

MILEAGE .10 x 5K x mile = 1964.00

TOTAL 10086.10

**SERVICE**

DEPTH OF JOB 2354'

PUMP TRUCK CHARGE 1185.00

EXTRA FOOTAGE @ \_\_\_\_\_

MILEAGE @ NA

MANIFOLD @ \_\_\_\_\_

TOTAL 1185.00

**PLUG & FLOAT EQUIPMENT**

@ \_\_\_\_\_

@ \_\_\_\_\_

@ \_\_\_\_\_

@ \_\_\_\_\_

@ \_\_\_\_\_

TOTAL \_\_\_\_\_

SALES TAX (If Any) \_\_\_\_\_

TOTAL CHARGES \_\_\_\_\_

DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS

9116.20