

CONFIDENTIAL

ORIGINAL 3/26/10

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

Form ACO-1
October 2008
Form Must Be Typed

WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE

OPERATOR: License # 5004
Name: Vincent Oil Corporation
Address 1: 155 N. Market, Ste 700
Address 2: _____
City: Wichita State: Kansas Zip: 67202 + 1821
Contact Person: M.L. Korphage
Phone: (316) 262-3573
CONTRACTOR: License # 5929
Name: Duke Drilling Co. Inc.
Wellsite Geologist: Ken LeBlanc
Purchaser: _____
Designate Type of Completion:
 New Well Re-Entry Workover
 Oil SWD SIOW
 Gas ENHR SIGW
 CM (Coal Bed Methane) Temp. Abd.
 Dry Other _____
(Core, WSW, Expl., Cathodic, etc.)

If Workover/Re-entry: Old Well Info as follows:
Operator: _____
Well Name: _____
Original Comp. Date: _____ Original Total Depth: _____
 Deepening Re-perf. Conv. to Enhr. Conv. to SWD
 Plug Back: _____ Plug Back Total Depth _____
 Commingled Docket No.: _____
 Dual Completion Docket No.: _____
 Other (SWD or Enhr.?) Docket No.: _____
11-28-2008 12-11-2008 1/06/2009
Spud Date or Date Reached TD Completion Date or Recompletion Date

API No. 15 - 057-20624-00-00
Spot Description: S/2-SW-NW-NW
S/2 SW NW NW Sec. 12 Twp. 29 S. R. 23 East West
1090 Feet from North / South Line of Section
380 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Ford
Lease Name: Clevenger Well #: 1-12
Field Name: Wildcat
Producing Formation: Morrow
Elevation: Ground: 2523 Kelly Bushing: 2535
Total Depth: 5427 Plug Back Total Depth: 5400
Amount of Surface Pipe Set and Cemented at: 620 Feet
Multiple Stage Cementing Collar Used? Yes No
If yes, show depth set: _____ Feet
If Alternate II completion, cement circulated from: _____
feet depth to: _____ w/ API-Log 4/17/09 ^{5x crnt}

Drilling Fluid Management Plan
(Data must be collected from the Reserve Pit)
Chloride content: 21,000 ppm Fluid volume: 1800 bbls
Dewatering method used: Allow to dry by evaporation, backfill and level
Location of fluid disposal if hauled offsite: _____
Operator Name: _____
Lease Name: _____ License No.: _____
Quarter _____ Sec. _____ Twp. _____ S. R. _____ East West
County: _____ Docket No.: _____


INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: M.L. Korphage
Title: Geologist Date: 3-26-2009

Subscribed and sworn to before me this 26th day of March, 2009.

Notary Public: Yolanda Eubanks
Date Commission Expires: _____



KCC Office Use ONLY
 Letter of Confidentiality Received
 If Denied, Yes Date: _____
 Wireline Log Received
 Geologist Report Received
 UIC Distribution
RECEIVED
KANSAS CORPORATION COMMISSION

MAR 26 2009
CONSERVATION DIVISION
WICHITA, KS

ALLIED CEMENTING CO., LLC. 32965

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT: Great Bend
~~Mad. Lodge, Ks~~

DATE <u>11-28-08</u>	SEC. <u>12</u>	TWP. <u>29</u>	RANGE <u>23w</u>	CALLED OUT <u>3:00 PM</u>	ON LOCATION <u>6:00 PM</u>	JOB START <u>11:00 PM</u>	JOB FINISH <u>11:30 PM</u>
LEASE <u>Cleenger</u>	WELL # <u>1-12</u>	LOCATION <u>Kingsdown, Ks - 1N, 2W,</u>			COUNTY <u>Ford</u>	STATE <u>Ks</u>	
OLD OR <input checked="" type="radio"/> NEW (Circle one)			<u>5/5</u>				

CONTRACTOR Duke #1

TYPE OF JOB Surface

HOLE SIZE 12 1/4" T.D. 620'

CASING SIZE 8 5/8" DEPTH 619'

TUBING SIZE _____ DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX 500# MINIMUM 0

MEAS. LINE _____ SHOE JOINT 40'

CEMENT LEFT IN CSG. 40'

PERFS. _____

DISPLACEMENT 36.88 BBLs of freshwater

OWNER Vincent oil

CEMENT

AMOUNT ORDERED 425 5x Common

3% CC, 2% Gel

EQUIPMENT

PUMP TRUCK CEMENTER Rick H.

181 HELPER Alvin R.

BULK TRUCK

482-112 DRIVER Ron H.

BULK TRUCK

_____ DRIVER _____

COMMON	<u>425</u>	@ <u>15.45</u>	<u>6,566.25</u>
POZMIX		@	
GEL	<u>9</u>	@ <u>20.80</u>	<u>187.20</u>
CHLORIDE	<u>13</u>	@ <u>58.20</u>	<u>756.60</u>
ASC		@	
RECEIVED			
KCC			
MAR 26 2009			
CONFIDENTIAL			
KANSAS CORPORATION COMMISSION			
MAR 26 2009			
CONSERVATION DIVISION			
WICHITA, KS			
HANDLING	<u>447</u>	@ <u>2.40</u>	<u>1072.80</u>
MILEAGE	<u>447 x .10 x 55</u>	=	<u>2,458.50</u>
			TOTAL <u>11,041.35</u>

REMARKS:

pipe on bottom, break circulation,
mixed 425 5x 3% CC, 2% gel, shut down
Released plug + displaced with 36.88
BBLs of freshwater + shut in.

Cement did circulate!

SERVICE

DEPTH OF JOB	<u>619'</u>		<u>1,018.00</u>
PUMP TRUCK CHARGE	<u>0-300'</u>		<u>1,018.00</u>
EXTRA FOOTAGE	<u>319'</u>	@ <u>.85</u>	<u>271.15</u>
MILEAGE	<u>55</u>	@ <u>7.00</u>	<u>385.00</u>
MANIFOLD		@	
<u>Head Rent</u>		@ <u>113.00</u>	<u>113.00</u>
			<u>1787.15</u>
			TOTAL <u>2,002.00</u>

CHARGE TO: Vincent oil

STREET _____

CITY _____ STATE _____ ZIP _____

PLUG & FLOAT EQUIPMENT

<u>8 5/8"</u>	@		
<u>1- Rubber plug</u>	@ <u>113.00</u>		<u>113.00</u>
<u>1- Baffle plate</u>	@ <u>152.00</u>		<u>152.00</u>
			TOTAL <u>265.00</u>

To Allied Cementing Co., LLC.

You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

SALES TAX (If Any) _____

TOTAL CHARGES _____

DISCOUNT _____ IF PAID IN 30 DAYS

PRINTED NAME X Mike Godfrey

SIGNATURE X Mike Godfrey

ALLIED CEMENTING CO., LLC. 043176

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

Medicine Lodge

DATE <u>12/12/08</u>	SEC. <u>12</u>	TWP. <u>29S</u>	RANGE <u>23W</u>	CALLED OUT <u>12:30 A.M.</u>	ON LOCATION <u>3:00 A.M.</u>	JOB START <u>5:30 A.M.</u>	JOB FINISH <u>6:30 A.M.</u>
LEASER <u>Clevenger</u>	WELL # <u>1-12</u>		LOCATION <u>Kingsdown, Ka. 1N, 2W,</u>			COUNTY <u>Ford</u>	STATE <u>Ks</u>
OLD OR <u>NEW</u> (Circle one)			<u>s/into</u>				

CONTRACTOR Duke #1
 TYPE OF JOB production
 HOLE SIZE 7 7/8 T.D. 5420'
 CASING SIZE 4 1/2 DEPTH 5400'
 TUBING SIZE _____ DEPTH _____
 DRILL PIPE _____ DEPTH _____
 TOOL _____ DEPTH _____
 PRES. MAX 1700 MINIMUM _____
 MEAS. LINE _____ SHOE JOINT 42'
 CEMENT LEFT IN CSG. _____
 PERFS. _____
 DISPLACEMENT 860# BBLs 2% KCl/H₂O

OWNER Vincent Oil Co.

CEMENT
 AMOUNT ORDERED 2000# ASC + 5 # Kol Seal
1.5% FL-160
Clapro 9 gals 500 gds ASF

RECEIVED
KANSAS CORPORATION COM

MAR 26 2009

CONSERVATION DIVIS

WICHITA, KS

COMMON	@		
POZMIX	@		
GEL	@		
CHLORIDE	@		
ASC <u>200</u>	@	<u>18.60</u>	<u>3720.00</u>
<u>Kol Seal 1000#</u>	@	<u>.89</u>	<u>890.00</u>
<u>Clapro 9 gals.</u>	@	<u>31.25</u>	<u>281.25</u>
<u>FL-160 94#</u>	@	<u>13.30</u>	<u>1250.20</u>
<u>ASF 500 gl.</u>	@	<u>1.27</u>	<u>635.00</u>

EQUIPMENT
 PUMP TRUCK CEMENTER Mark C.
 # 360-265 HELPER Steve K.
 BULK TRUCK
 # 381-314 DRIVER Randy E.
 BULK TRUCK
 # _____ DRIVER _____

KCC

MAR 26 2009

CONFIDENTIAL

HANDLING <u>257</u>	@	<u>2.40</u>	<u>616.80</u>
MILEAGE <u>55 X 257 X 10</u>			<u>1413.50</u>
TOTAL			<u>8806.75</u>

REMARKS:

Pipe on bottom, leak Circ. pump 500 gals ASF.
plug ret mouse w/255x. mly 1785x ASC.
Stop wash pump lines. release plug.
Disp. w/2% KCl H₂O. See left. Slow
rate. Pump plug 500 over @ 860.5 BBLs.
Float did hold

SERVICE

DEPTH OF JOB <u>5400'</u>			
PUMP TRUCK CHARGE			<u>2295.00</u>
EXTRA FOOTAGE	@		
MILEAGE <u>55</u>	@	<u>7.00</u>	<u>385.00</u>
MANIFOLD	@		
<u>Head Rental</u>	@	<u>11.300</u>	<u>113.00</u>
TOTAL			<u>2793.00</u>

CHARGE TO: Vincent Oil Co.
 STREET _____
 CITY _____ STATE _____ ZIP _____

PLUG & FLOAT EQUIPMENT

<u>1- Guide shoe</u>	@	<u>169.00</u>	<u>169.00</u>
<u>1- AFU Insert</u>	@	<u>254.00</u>	<u>254.00</u>
<u>Co-Centrators</u>	@	<u>51.00</u>	<u>306.00</u>
<u>1- Rubber plug</u>	@	<u>62.00</u>	<u>62.00</u>

TOTAL 791.00

To Allied Cementing Co., LLC.
 You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PRINTED NAME Pat Livingston

SIGNATURE Pat Livingston

SALES TAX (If Any) _____

TOTAL CHARGES ~~2793.00~~

DISCOUNT ~~1413.50~~ IF PAID IN 30 DAYS

ANY APPLICABLE TAX
 WILL BE CHARGED
 UPON INVOICING