

MAR 24 2010

RECEIVED  
KANSAS CORPORATION COMMISSION

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING APPLICATION**  
Please TYPE Form and File ONE Copy

Form CP-1  
March 2009  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 33384  
Name: High Bluff Operating, LLC  
Address 1: 730 17th Street, Suite 700  
Address 2: \_\_\_\_\_  
City: Denver State: CO Zip: 80202 + \_\_\_\_\_  
Contact Person: Jamie Brown  
Phone: (303) 295-2223

API No. 15 - 025-21307 0000  
If pre 1967, supply original completion date: \_\_\_\_\_  
Spot Description: NW  
NW Sec. 14 Twp. 34 S. R. 25  East  West  
1.320 Feet from  North /  South Line of Section  
1.320 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Clark  
Lease Name: Cauthers Well #: 4

Check One:  Oil Well  Gas Well  OG  D&A  Cathodic  Water Supply Well  Other: \_\_\_\_\_  
 SWD Permit #: \_\_\_\_\_  ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Conductor Casing Size: NONE Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks  
Surface Casing Size: 8 5/8 Set at: 711' Cemented with: 400 Sacks  
Production Casing Size: 4 1/2 Set at: 5750' Cemented with: 200 Sacks

List (ALL) Perforations and Bridge Plug Sets:  
CIBP at 5672', Perfs 5658-5666, and 5634-5642'

Elevation: 2033 ( G.L. /  K.B.) T.D.: 5750' PBTD: 5703' Anhydrite Depth: 1050'  
(Stone Corral Formation)  
Condition of Well:  Good  Poor  Junk in Hole  Casing Leak at: \_\_\_\_\_  
(Interval)  
Proposed Method of Plugging (attach a separate page if additional space is needed):

Set CIBP at 5584' with 4 sacks of cement on top, Cut casing and pull aprox. 4000', set cement plug at 1050' with 125 sacks, next plug at 250' with 40 sacks, next plug at 40' with 20 sacks. 60/40 pos with 4% gel. Per Mike from Dodge City office.

Is Well Log attached to this application?  Yes  No Is ACO-1 filed?  Yes  No  
If ACO-1 not filed, explain why:

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission  
Company Representative authorized to supervise plugging operations: Rodney Gonzales  
Address: Box 816 City: Lakin State: Ks Zip: 67860 + \_\_\_\_\_  
Phone: (620) 655-6891  
Plugging Contractor License #: 99996 Name: Allied Cementing  
Address 1: Box 31 Address 2: \_\_\_\_\_  
City: Russell State: ks Zip: 67665 + 0031  
Phone: (785) 483-2627  
Proposed Date of Plugging (if known): 3-30-2010

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent  
Date: 3-24-2010 Authorized Operator / Agent: Rodney Gonzales (Signature)

*Handwritten:* KCC  
3/26/10

*Handwritten:* KCC  
pw



CORPORATION COMMISSION

Mark Parkinson, Governor Thomas E. Wright, Chairman Joseph F. Harkins, Commissioner

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

HIGH BLUFF OPERATING LLC  
730 17TH ST STE 700  
DENVER, CO 80202-3539

March 26, 2010

Re: CAUTHERS #4  
API 15-025-21307-00-00  
14-34S-25W, 1320 FNL 1320 FWL  
CLARK COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

**This notice is void after September 22, 2010. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.**

Sincerely

Steve Bond  
Production Department Supervisor

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(620) 225-8888