

119.24

01
ka
ap3

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-19210-00-00
Spot: SWSWSW Sec/Twnshp/Rge: 12-18S-10W
317 feet from S Section Line, 4713 feet from E Section Line
Lease Name: ANNA HABIGER Well #: 1
County: RICE Total Vertical Depth: 3669 feet

Operator License No.: 33725
Op Name: FOUNDATION ENERGY MANAGEMENT
Address: 14800 LANDMARK BLVD STE 220
DALLAS, TX 75254

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	195		120 SX
PROD	4.5	3277		100 SX

Well Type: SWD UIC Docket No: D14375.0 Date/Time to Plug: 01/20/2010 9:00 AM
Plug Co. License No.: 7868 Plug Co. Name: KIZZAR WELL SERVICING, INC.
Proposal Rcvd. from: DAVID KOSS Company: FOUNDATION ENERGY MGMT Phone: (620) 786-4161

Proposed Plugging Method: SAND TO OR SET CIBP @ 3220' AND CAP WITH 2SX'S CEMENT, PERFORATE @ 1200', 850' AND 250'. RUN TU;BING TO 1220' AND PUMP 50 SX'S, LET SET AND TAG. RUN TUBING TO 850' AND PUMP 50 SX'S. PULL TUBING TO 250' AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF.

Plugging Proposal Received By: SHANE JONES WitnessType: PARTIAL
Date/Time Plugging Completed: 01/20/2010 4:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:
MIRU, CK BOTTOM. RUN CIBP DOWN SLUGGISHLY TO 3050' AND CAP WITH 2.5 SX'S CEMENT. PERFORATE @ 1200', 850', AND 250'. RUN TUBING TO 1200' AND PUMP 50 SX'S CEMENT--LET SET FOR AWAHILE AND TAGGED @ 825'. PUMP 35 SX'S CEMENT @ 850'. PULL TUBING TO 250' AND CIRCULATE CEMENT TO SURFACE--AND ALSO ON BACKSIDE OF CASING. PULL TUBING OUT AND TOP OFF. USED TOTAL OF 385 SX'S CEMENT PER NATHAN WITH COPELAND.

Perfs:

Top	Bot	Thru	Comments
3277	3669		OPEN HOLE

INVOICED
DATE 2/25/10
INV. NO. 2010060788

RECEIVED
FEB 05 2010
KCC WICHITA

Remarks: 60-40 POZ, 4% GEL. COPELAND TICKET #C-36297. GPS READING INDICATES 292' FSL & 4613' FEL.
Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

VJK