

#109.20

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-21154-00-02  
Spot: NWSESE Sec/Twnshp/Rge: 19-20S-9W  
707 feet from S Section Line, 996 feet from E Section Line  
Lease Name: MALONE EDWARD Well #: 1  
County: RICE Total Vertical Depth: 3360 feet

Operator License No.: 33725  
Op Name: FOUNDATION ENERGY MANAGEMEN  
Address: 14800 LANDMARK BLVD STE 220  
DALLAS, TX 75254

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2165		
CIBP		3255		
SURF	8.625	211		150 SX 60/40 POZ 2%GEL,3%C.C
PROD	4.5	3359		100 SX 50/50 POZ 2%GEL

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/25/2009 1:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE Phone: (620) 562-8088

Proposed Plugging Method: CIBP @ 2165'. CAP WITH 2 SX'S CEMENT. PERFORATE @ 1250', 850', AND 250'. RUN TUBING TO 1250 AND PUMP 35 SX'S CEMENT, PULL TO 850' AND PUMP 35 SX'S, PULL 250' AND CIRCULATE CEMENT TO SURFACE.

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL  
Date/Time Plugging Completed: 11/27/2009 11:15 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU: A CIBP ALREADY SET @ 2165. CAP CIBP WITH 2 SX'S CEMENT. PERFORATE @ 1250', 850', AND 250'. RUN TUBING TO 1250' AND PUMP 50 SX'S CEMENT. PULL TUBING TO 850'. LET SET FOR 1 HR. AND TRY TO TAG CEMENT - COULD NOT. RUN TUBING BACK DOWN TO 1250' AND PUMP 35 SX'S CEMENT. PULL TUBING TO 850' LET SET FOR 1 HR. AND TRY TO TAG CEMENT--COULD NOT. RUN TUBING BACK DOWN TO 1250' AND PUMP 35 MORE SX'S CEMENT, PULL TUBING ON OUT. 11-27-2009, TAGGED CEMENT @ 160'. RUN TUBING TO 150' AND CIRCULATE CEMENT TO SURFACE. CONNECTED ON TO BACKSIDE OF CASING AND PUMP CEMENT UP TO 400#'S--HELD PRESSURE. USED APPROX. 160 SX'S CEMENT.

Perfs:

Top	Bot	Thru	Comments
3305		CSG	SIMPSON
2215		CSG	TARKIO

INVOICED

DATE 2/25/10

INV. NO. 2010060780

RECEIVED

FEB 05 2010

KCC WICHITA

Remarks: 60-40 POZ, 4% GEL. LOG TECH OF KS TICKET 35874. COPELAND CEMENT TICKET #C-35641.

Plugged through: TBG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

JK