

15-065-20845-0000

To: 6 030901  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 8 - 16 - 76

NE NW SW, SEC. 23, T 10 S, R 25 W/E  
2310 feet from S section line  
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5364

Lease Name Schreiner Well # 1 SWD  
County Graham 131.30

Operator: Beren Corp  
Name & Address: Box 723  
Hays, Kansas 67601

Well Total Depth 4040 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 238'

Abandoned Oil Well Gas Well Input Well SWD Well X D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050  
Address Chase, Kansas

Company to plug at: Hour: PM Day: 22 Month: June Year: 19 87

Plugging proposal received from Mark

(company name) Kelso Casing (phone)

were: 8 5/8 set at 238' w/165 sks 4 1/2 set at 4039' w/150 sks. Perfs.  
3800 - 3973 PBTD 4039'. Order sand and Com Cmt. Shoot and pull pipe.  
Order 200 sks ATL 65/35 Poz 10% Gel 2% Dical. Allied Cmt. Co. Wellbrock  
Water Trucks.

Plugging Proposal Received by Carl Goodrow  
(TECHNICIAN)  
Carl Goodrow

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 1:15 PM Day: 22 Month: June Year: 19 87

ACTUAL PLUGGING REPORT Dump sand on PBTD to 3750' w/4' sks Com Cmt. on sand w/bailer.

4 shots at 2500 1500 1300 1225. Recovered 1225' of 4 1/2" csg.  
Squeeze 8 5/8 w/200 ATL Max. Psi. 750#. Close in 200#. Plug complete.

RECEIVED  
STATE CORPORATION COMMISSION  
7-16-87  
JUL 16 1987  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: (if additional description is necessary, use BACK of this form.)

INVOICED  
I (and/or ~~XXXXXX~~) observe this plugging.

DATE 7-16-87  
INV. NO. 17505

Signed Carl Goodrow  
(TECHNICIAN)  
Carl Goodrow