

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-00777-00-00
Spot: CNWNWNE Sec/Twnshp/Rge: 23-10S-25W
4950 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: SCHREINER Well Number: 1
County: GRAHAM Total Vertical Depth: 4020 feet

Operator License No.: 31086
Op Name: RICHLAN DRILLING
Address: 598 - 2ND AVE.
BEAVER, KS 67525

Conductor Pipe: Size feet: 8 1/2
Surface Casing: Size 8.625 feet: 235
Production: Size 5.5 feet: 4020
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 06/19/2002 10:00 AM

Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.

Proposal Rcvd. from: RICK SCHREIBER Company: D S & W WELL SERVICING, INC. Phone: (620) 587-3605

Proposed Plugging Method: According to KCC Rules & Regulations.
Ordered 325 sxs cement and 500# hulls.

Plugging Proposal Received By: HERB DEINES

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 06/19/2002 4:30 PM

KCC Agent: ROGER MOSES

Actual Plugging Report:

8 5/8" S.P. at 235' w/225 sxs cement. 5 1/2" casing at 4020' w/125 sxs cement.
Ran tubing to 2130' - circulated with 20 sxs cement with 500# hulls.
Pulled all tubing and squeezed 5 1/2" with 125 sxs to Max. P.S.I. 800#. S.I.P. 500#.
Tied to 8 5/8" x 5 1/2" - took nothing at 300#.
Total of 325 sxs 60/40 pozmix - 10% gel - 500# hulls.

RECEIVED
7-8-02
JUL 08 2002
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY. WALKER TANK-WATER.

Plugged through: TBG

District: 04

Signed

Roger L. Moses
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 7-8-02

WELL NO. 2003060010


JUL 01 2002

HERNDON DRLG CO #1 SCHREINER 23-10-25W
 NW NW NE
 Contr. HERNDON DRLG GRAHAM County
 E 2446RB Comm. 11-6-59 Comp. 12-4-59 IP 240 BOPD

Tops	Depth	Datum
HEEB	3707	-1261
TOR	3731	-1285
LANS	3748	-1302
B/KC	3944	-1498
TD	4020	-1574

Casing
 8" 235
 5" 4020
 DST 3717-60/90", G/15", 1500#
 OIL, BHP 1260#
 PERF 3920-28: ACID 1000: SWB
 5' BOPH, NW

ELRICK SE



INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS