

8-26

15-005-30367-0000

4-041523

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- -
SE
SW NE ~~SW~~ /4 SEC. 09, 10 S, 25 W
1650 feet from S section line
3630 890 feet from E section line
ZIKLL

Operator license# 3553 Lease Elrick well # 8-4

Operator: Citation Oil & Gas Corporation County Graham

Address: 8223 Willow Place S. Well total depth 4225 feet 137.31
Suite 250 Conductor Pipe: 0 inch @ 0 feet
Houston, Texas 77070 Surface pipe 8 5/8 Inch @ 248 feet
w/175 sx cwc.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00A.M. Day: 26 Month: August Year: 93

Plugging proposal received from: Verland Duggan

Company: Citation Oil & Gas Corporation Phone:

Were: 5 1/2" casing set @ 4212' w/150 sxs.cement. Perf. @ 3762'-4003'.
Anhy. @ 2150' - Dakota @ 1250'.
Ordered 500 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 5:30P.M., Day: 26, Month: August, Year: 93

Actual plugging report: R.I.H. w/tbq.to 4026'. Spotted 90 sxs.cement with
400# hulls. Pulled up to 2158'. Spot 100 sxs. cement with 200# hulls.
Pull to 1251'. Spot and circulate cement to surface with 100 sxs. cement
Squeeze 5 1/2" casing with 50 sxs. cement. Max. 700#. Squeeze 8 5/8"
S.P. with 150 sxs. cement. Max. 300# P.S.I.

Remarks:
Condition of casing(in hole): GOOD BAD X Anhy.plug: YES X NO
Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING. Elevation: GL

I did not [X] observe the plugging.

RECEIVED
STATE CORPORATION COMMISSION
OCT 20 1993
Dennis L. Hamel
NO (agent)
Form CP-2/3 CONSERVATION DIVISION
Wichita, Kansas

INVOICED
DATE 10-21-93
INV. NO. 38996