

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-065-21, 732 10000
SE, Sec. 23, T 10 S, R 25 W/E
1650 feet from N 15 section line
990 feet from W 15 section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7572

Lease Name Kindernacht Well # 1

Operator: Mergo Oil & Refiners
Name & Address P.O. Box 12666, 2525 Ridgman Blvd.
Fourth Month, TX, 76116

County Gravham

Well Total Depth 4060 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 266'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Aldreiten Drilling License Number 363

Address P.O. Box 18611, Wichita, Mo. 67207

Company to plug at: Hour: 9:00 AM Day: 19 Month: 12 Year: 19 82

VERBAL PLUGGING ORDERS GIVEN TO Duke Harmon

(company name) Aldreiten Drilling (phone) _____

were: Order 190 sacks 50 permix - 6% cel. - 3% Col. & 8 5/8" plug. Spot w/drill
stem w/ heavy mud between all plugs. 1st plug C 2160' w/20 sh.
2nd plug C 1000' w/100 sh. 3rd plug C 300' w/40 sh. 4th plug - solid
bridge of balls & plug C 40' w/10 sh.

Circulate 10 sh in rat hole & 10 sh in mouse hole.

Signed Ruth E. Loh
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 9:15 AM Day: 19 Month: 12 Year: 19 82

ACTUAL PLUGGING REPORT 8 5/8" - 266' w/165 sh. common. - 2% cel. - 3% Col. U.

Ordered 190 sacks 50 permix - 6% cel. - 3% Col. U. & 8 5/8" plug. Spot w/drill
stem w/ heavy mud between all plugs. 1st plug C 2160' w/20 sh.
2nd plug C 1000' w/100 sh. 3rd plug C 300' w/40 sh. 4th plug - solid
bridge of balls & plug C 40' w/10 sh.

Circulated 10 sh in rat hole & 10 sh in mouse hole.

Remarks: No. Arbuckle.

RECEIVED
STATE CORPORATION COMMISSION

JAN 10 1983

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated
and that I (~~did~~/ did not) observe this plugging.

INVOICED

DATE 1-3-83

INV. NO. 2302-W

Signed Ruth E. Loh
(TECHNICIAN)