

3-11
4-032209

15-065-00617-0000
R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 1956

S2 SE NE /4 SEC. 16 , 10 , 25 W
2970 feet from S section line
660 feet from E section line

Operator license# -

Lease: Knoll Well # 2

Operator: State of Kansas Fee Fund

County: Graham

Address: 2301 E. 13th Street - Dist. #4
Hays, Kansas 67601
Project #970155

Well total depth 3992 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 194 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 11 Month: March Year: 1997

Plugging proposal received from: Carl Goodrow - Herb Deines

Company: State of Kansas Fee Fund Phone: 913-628-1200

Were: Order 200 sxs 60/40 pozmix - 10% gel - 200# hulls.

Visual inspection indicated casing pulled and possibly plugged, but no plugging report filed.
Could find no verification of what had been done to the well.

RECEIVED
KANSAS CORP COM
1997 MAR 19 A 3
3-19-98

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 9:30 A.M., Day: 11, Month: March, Year: 1997

Actual plugging report: Cut off old head and rebuild 8 5/8" plate and collar to plug through. Tied onto new collar. Mixed and pumped down 8 5/8" 200 sxs cement blend with 200# hulls to Max. P.S.I. 500#. Close in P.S.I. 100#. Plug complete. Backfilled and leveled location.

Remarks:
Condition of casing(in hole): GOOD BAD Any plug: YES X NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES X, NO
Plugged through TUBING , CASING . Elevation: GL

I did[X] / did not[] observe the plugging.
OKD

Carl Goodrow
(agent)

15-065-00617-0000
#2
SR

TO BE IN
SEP 1 1961
CONSERVATION DIVISION
Wichita, Kansas

LOG

COMPANY: EMPIRE DRILLING COMPANY, WICHITA, KANSAS

CONTRACTOR: EMPIRE DRILLING COMPANY, WICHITA, KANSAS

FARM: C. KNOLL NO. 2

LOCATION: CENTER S/2 SE/4 NE/4 OF SEC. 16-10-25W, GRAHAM COUNTY, KANSAS

COMMENCED: OCTOBER 5, 1958

ELEVATION: 2507 K.B.

COMPLETED: OCTOBER 20, 1958

POTENTIAL:


0	TO	1260	SHALE AND SAND	TOPS:	
1260	TO	1710	SHALE		
1710	TO	2160	SHALE AND SHELLS	TOPEKA	3530
2160	TO	2165	ANHYDRITE	NEEDNER	3742
2165	TO	2840	SHALE AND SHELLS	TORONTO	3765
2840	TO	3160	SHALE AND LIME	LANSING KANSAS CITY	3787
3160	TO	3310	LIME AND SHALE		
3310	TO	3384	SHALE AND SHELLS		
3384	TO	3580	LIME AND SHALE		
3580	TO	3370	SHALE AND LIME		
3370	TO	3780	LIME AND SHALE		
3780	TO	3992	LIME		
3992			R.T.D.		

CASING RECORD: RAN 194' OF 8 5/8" AND CEMENTED WITH 115 SACKS CEMENT.
SET 3991' OF 5 1/2" CASING AND CEMENTED WITH 75 SACKS POSMIX CEMENT.

RAN SCHLUMBERGER ELECTRIC LOG.

CERTIFICATION

I, DAN J. KORNFELD, DO HEREBY CERTIFY THAT THE ABOVE AND FOREGOING IS A TRUE AND CORRECT COPY OF THE LOG ON THE C. KNOLL NO. 2, CENTER S/2 SE/4 NE/4 OF SEC. 16-10-25W, GRAHAM COUNTY, KANSAS, AS REFLECTED BY THE FILES OF THE EMPIRE DRILLING COMPANY.


DAN J. KORNFELD

SUBSCRIBED AND SWORN TO BEFORE ME, A NOTARY PUBLIC WITHIN AND FOR SEDGWICK COUNTY, KANSAS, THIS 14TH DAY OF OCTOBER, 1958.


NOTARY PUBLIC

My Commission Expires Oct. 21, 1958