

6 031323

API NUMBER 15-

1971

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

C NW SW NESEC. 22, T 10 S, R 25 WAE

3630 feet from S section line

2310 feet from E section line

Lease Name Knoll Well # 2

County Graham 131.63

Well Total Depth 4050 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 210

TECHNICIAN'S PLUGGING REPORT

Operator License # 5364

Operator: Beren Corp  
Name & Address: Box 723  
Hays, Ks. 67601

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor B. J. Titan License Number

Address Hays, Ks.

Company to plug at: Hour: AM Day: 16 Month: Dec Jan Year: 19 89 90

Plugging proposal received from Bob Grant

(company name) Beren (phone)

were: 8 5/8" set at 210' w/170 sks. 5 1/2" set at 4049' w/200 sks. Perf 4000-05.

Two shot holes at 1330' Order 350 sks 65/35 poz 10% gel 2% A-2 500# hulls.

B. J. Titan Cement Co. Okmar Beren rig. Wellbrock water.

Plugging Proposal Received by CARL

(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 12:30PM Day: 16 Month: Dec Jan Year: 19 89 90

ACTUAL PLUGGING REPORT Ran tubing to 3932' 400# hulls in 200 sks circulate cement

blend to surface. Tie onto 5 1/2" squeeze w/25 sks to max psi 900#. Close in psi 900#.

Squeeze 8 5/8" w/100 sks cement blend to max psi 500#. Close in psi 500#. Plug

complete.

RECEIVED  
STATE CORPORATION COMMISSION  
1-26-1990  
JAN 26 1990

Remarks: (If additional description necessary, use BACK of this form.)

Observe this plugging.

INVOICED

DATE FEB 05 1990

INV. NO. 27309

Signed Carl Goodrow (TECHNICIAN)  
Carl Goodrow