

6 031322

API NUMBER 15- 1971

15-065-20243-00-00 27 1/2 R
12-15

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW NW SE, SEC. 22, T 10 S, R 25 W Ex
2310 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5364

Lease Name Knoll Well # 1

Operator: Beren Corp

County Graham 130.55

Name & Address Box 723

Well Total Depth 4017 feet

Hays, Ks. 67601

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 210

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor B. J. Titan License Number

Address Hays, Kansas

Company to plug at: Hour: PM Day: 15 Month: Jan Dec Year: 19 90

Plugging proposal received from Bob Grant

(company name) Beren (phone)

were: 8 5/8" set at 210 w/170 sks. 4 1/2" set at 4017'. Perf 3803' - 2982

Order 300 sks 65/35 poz 10% gel 2% A-Z B. J. Titan Cement Co. Okmar. Beren rig. Well-
brock water truck. Shot at 1330' (below dk) Hole in dakota, break in.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:10PM Day: 15 Month: Dec Year: 19 90

ACTUAL PLUGGING REPORT Run tubing to 3932' w/145 sks circulate cement blend to surface w/100# hulls in cement. Squeeze 4 1/2" w/15 sks. Max psi 800# Close in psi 800 psi. Squeeze 8 5/8" w/100 sks cement blend w/150# hulls mixed into max psi 400#. Close in psi 400#. Plug complete.

RECEIVED
STATE CORPORATION COMMISSION
1-26-1990
JAN 26 1990

Remarks: (If additional description is necessary, use BACK of this form.)

(I did / did not) observe this plugging.

INVOICED

DATE FEB 05 1990

INV. NO. 27308

Signed Carl Goodrow (TECHNICIAN)

Carl Goodrow