

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-20269-00-01
Spot: CSESENW Sec/Twnshp/Rge: 22-10S-25W
2970 feet from S Section Line, 2970 feet from E Section Line
Lease/Unit Name: BRUNGARDT B Well Number: 1
County: GRAHAM Total Vertical Depth: 4080 feet

Operator License No.: 5363
Op Name: BEREXCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

Production Casing Size: 4.5 feet: 4080 w/135 sxs cmt 132.60
Surface Casing Size: 8.625 feet: 208 w/175 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/26/2003 1:00 PM
Plug Co. License No.: 5363 Plug Co. Name: BEREXCO, INC.
Proposal Rcvd. from: CURT GABEL Company: BEREXCO, INC. Phone: (785) 628-6101

Proposed Plugging Method: Ordered out 310 sxs 60/40 pozmix - 10% gel - 600# hulls.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 03/26/2003 6:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:
Swaged onto 4 1/2" - mixed and pumped 215 sxs cement with 600# hulls.
S.I.P. 600#.
Hooked up to 8 5/8" and pumped 95 sxs cement.
S.I.P. 100#.

RECEIVED
4-1-2003
APR 01 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.
Plugged through: CSG

District: 04

Signed *J.P. Pfeifer*
(TECHNICIAN)

MAR 27 2003

INVOICED
DATE 4-1-03
INV. NO. 2003061368

DERRICK AMERICAN OIL COMPANY #1 BRUNGARDT 'B' 22-10-25W
 WICHITA, KS. SE SE NW

Contr. GABBERT-JONES City GRAHAM

Geol. JIM THOMPSON Pool AMBROSE

E. 2532 RB. Cm. 10/18/69 Cp. 1/15/70 IP PMP -156 BOPD, NW/
 LANS 4004-11, GR 38

API 15-065-20,269

SMP Tops	Depth	Datum	Csg.
ANH	2161	+ 371	8" 208/175 sx; 4 1/2" 4080/135 sx
B ANH	2209	+ 323	DST (1) 3718-3740/60", 510' W, FBHP 1118#/ 20", FP 80-282#
HEEB	3782	-1250	DST (2) 3747-3758/1', 1050' SW, FBHP 1253#/ 20", FP 56-548#
TOR	3804	-1272	DST (3) 3789-3814/1', 330' HOCM, BHP 1225#/ 20", FP 60-130#
LKC	3818	-1286	DST (4) 3821-3840/1', 2880' SW, BHP 1347#/ 20", FP 686-1347#
RTD	4080	-1548	DST (5) 3840-3880/1', 300' HO&GCM, 1800' O&GCW, 300' W, FBHP 1364#, FP 306-1196#
			DST (6) 3880-3914/1', 60' GIP, 60' VHO&GCM 120' MO, FBHP 1331#/20", FP 42-97#
			DST (7) 3914-3990/1', GTS 1860' CO, FBHP 1266#/20", FP 283-860#
			CO & PF 24/4004-11, SWB 24 BO. NAT/45", POP NO LOG

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS