

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-22803-00-00
Spot: SENE Sec/Twnshp/Rge: 22-10S-25W
4290 feet from S Section Line, 330 feet from E Section Line
Lease/Unit Name: KNOLL C Well Number: 1
County: GRAHAM Total Vertical Depth: 4050 feet

Operator License No.: 32552
Op Name: ENERGY ONE OIL OPERATIONS
Address: 1116 EAST EIGHT ST
HAYS, KS 67601

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 209 W/140 SXS
Production: Size feet:
Liner: Size feet: 131.63

Well Type: DH UIC Docket No: Date/Time to Plug: 01/06/2001 1:00 PM
Plug Co. License No.: 30076 Plug Co. Name: A & A PRODUCTION
Proposal Rcvd. from: DARREL ANDERSON Company: A & A PRODUCTION Phone: (785) 421-6266

Proposed Plugging Method: Order 185 sxs 60/40 pozmix - 6% gel - 8 5/8" W.P
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CARL GOODROW
Date/Time Plugging Completed: 01/06/2001 2:00 PM

WitnessType: Plugging Operations Were Not Witnessed
KCC Agent: CARL GOODROW

Actual Plugging Report:

Spotted and displaced cement plugs.
1st. Plug at 2000' w/25 sxs.
2nd. Plug at 1180' w/100 sxs.
3rd. Plug at 250' w/40 sxs.
4th. Plug at 40' w/10 sxs. - 8 5/8" W.P.
10 sxs in rathole through joint of pipe.

RECEIVED
KANSAS CORPORATION COMMISSION
1-22-2001
JAN 22 2001
CONSERVATION DIVISION

Remarks: ALLIED CEMENTING COMPANY

Plugged through: DP

District: 04

Signed Carl Goodrow PERTIE
(TECHNICIAN)

KCC

INVOICED

Form CP-2/3

JAN 19 2001

DATE 1/22/01

JAN 16 2001

HAYS, KS

2001061345