

1-19

4-031896

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- -

SW NW SW /4 SEC. 22, 10 S, 25 W
1650 feet from S section line
4950 feet from E section line

Operator license# 5634

Lease Brungard well # A5

Operator: Beren Corporation

County Graham

Address: 970 Fourth Financial Center
Wichita, Kansas 67202

Well total depth 4079 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 315 feet

132.57

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 19 Month: January Year: 94

Plugging proposal received from: Bob Grant

Company: Beren Corporation Phone:

Were: Order 300 sxs. 65/35 pozmix - 10% gel - 500# hulls.
Fluid level near bottom - 4 joints up.

STATE MINERAL
FEB - 2 1994
2-2-1994

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 12:30 P.M., Day: 19, Month: January, Year: 94

Actual plugging report: 8 5/8" set @ 315' cwc. 265 sxs. 5 1/2" set @ 4079' w/125 sxs. P.B.T.D. 4064' - cement squeeze 2438' to surface cement in braden head. Prod. perf. 3819' - 4017'. Ran tubing to 2500'. Pumped 160 sxs. cement blend. Pulled tubing to 600'. Pumped 50 sxs. cement blend to circulate cement. Pulled tubing. Squeezed 5 1/2" with total 260 sxs. cement blend to Max. P.S.I. 500#. Close in P.S.I. 400#. Plug complete.

Remarks: Anhy. 2187' - 2224'.
Condition of casing (in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug (in place): YES, CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING. Elevation: GL

I did [X] did not [] observe the plugging. Carl Goodrow

INVOICED
DATE FEB 02 1994
INV. NO. 39841

HD (agent)
Form CP-2/3