

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-20336-00-00  
Spot: CSWNESW Sec/Twnshp/Rge: 22-10S-25W  
1650 feet from S Section Line, 3630 feet from E Section Line  
Lease/Unit Name: BRUNGARDT A Well Number: 2  
County: GRAHAM Total Vertical Depth: 4080 feet

Operator License No.: 5363  
Op Name: BEREXCO, INC.  
Address: PO BOX 20380  
WICHITA, KS 67208

Production Casing Size: 5.5 feet: 4079 w/125 sxs cmt 132.60  
Surface Casing Size: 8.625 feet: 207 w/150 sxs cmt

Well Type: OIL UIC Docket No: Date/Time to Plug: 03/26/2003 9:00 AM  
Plug Co. License No.: 5363 Plug Co. Name: BEREXCO, INC.  
Proposal Rcvd. from: CURT GABEL Company: BEREXCO, INC. Phone: (785) 628-6101

Proposed Plugging Method: Ordered out 360 sxs 60/40 pozmix - 10% gel - 600# hulls.  
Well squeezed at the following:  
2890'-3290' w/250 sxs.  
3310'-3346' w/125 sxs.  
1200'-1914' w/150 sxs.  
3420' w/250 sxs.  
1395'-1914' w/100 sxs.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 03/26/2003 1:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:  
TIH with tubing to 2000' - mixed and circulated cement with 110 sxs cement and 600# hulls.  
POOH and topped with 130 sxs cement.  
Max. P.S.I. 600#. S.I.P. 300#.  
Tied onto 8 5/8" and pumped 75 sxs.  
S.I.P. 100#.

**RECEIVED**  
*4-1-2003*  
**APR 01 2003**  
**KCC WICHITA**

Remarks: ALLIED CEMENTING COMPANY.  
Plugged through: TBG

District: 04

Signed *[Signature]*  
**(TECHNICIAN)**

**INVOICED**  
4-1-03  
2003061368

Form CP-2/3

**MAR 27 2003**

DERRICK-AMERICAN OIL, INC. #2 BRUNGARDT "A" 22-10-25W  
 WICHITA, KANSAS SW NE SW  
 CONTR GABBERT-JONES CTY GRAHAM  
 GEOL JIM THOMPSON FIELD AMBROSE  
 E 2535 KB CM 6/9/70 CARD ISSUED 7/30/70 IP P 100 BOPD + 10% WTR  
 LKC 3854-58 & 3863-69 (GR 42)

API 15-065-20,336

| LOG  | TOPS | DEPTH | DATUM |
|------|------|-------|-------|
| HEEB |      | 3786  | -1251 |
| TOR  |      | 3807  | -1272 |
| LKC  |      | 3821  | -1286 |
| RTD  |      | 4080  | -1545 |
|      |      |       |       |
|      |      |       |       |
|      |      |       |       |
|      |      |       |       |
|      |      |       |       |
|      |      |       |       |
|      |      |       |       |

8 5/8" 207/150SX; 5 1/2" 4079 1/2/125SX  
 DST(1) 3791-3817/1', GTS/46", REC 2570'  
 CO, BHP 1300-1280#, FP 250-210#  
 DST(2) 3825-3840/30", 60' GIP, 2800' WTR,  
 BHP 1355-1355#, FP 767-1322#  
 DST(3) 3843-3880/2', 3410' CGO, 120' MW,  
 BHP 1364-1364#, FP 759-1330#  
 DST(4) 3883-3920/1', 1740' OILY GSY W,  
 BHP 1310-1280#, FP 90-600#  
 DST(5) 3933-3989/1', 1500' GIP, 240' OCM,  
 780' O & GCW, BHP 1265-1240#, FP 137-451#  
 DST(6) 4001-4015/1', 5' DM, FBHP 613#,  
 FP 20-20#  
 DST(7) 4010-4035/1', 10' DM, FBHP 768#,  
 FP 24-24#  
 MICT PF 3854-58, 3863-69 KICKED BACK  
 30BOPD, NAT, N/W EST P 120-130 BOPD

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS